

SCHEDULE OF QUANTITIES

70301000	WORK ZONE PAVEMENT MARKING REMOVAL		NOTE
	SQ.FT	LOCATION	
		US Rte 6	
	110	RT 370+45.00 - 373+75.00	STAGE 1 EDGE LINE
	110	RT 394+30.08 - 397+60.08	STAGE 1 EDGE LINE
	835	RT 372+55.83 - 397+60.14	STAGE 2 LT EDGE LINE
	1670	RT 372+54.93 - 397+60.07	STAGE 2 CENTERLINE
	768	RT 374+54.74 - 397+60.07	STAGE 2 RT EDGE LINE
	28	LT 374+00.01 - 394+05.08	SHT TRM SHOULDER DIAGONALS
	88	LT 385+25.08 - 387+90.08	SHT TRM TURN LANE
	5	LT 385+45.08	SHT TRM ARROW
	5	LT 386+20.08	SHT TRM ARROW
	5	LT 386+95.08	SHT TRM ARROW
	5	LT 387+70.08	SHT TRM ARROW
	58	CL 374+00.01 - 375+73.68	SHT TRM CENTERLINE
	17	CL 393+55.08 - 394+05.08	SHT TRM CENTERLINE
	577	LT & RT 375+73.68 - 384+39.87	SHT TRM MEDIAN
	553	LT & RT 385+25.08 - 393+55.08	SHT TRM MEDIAN
	100	RT 381+38.68 - 384+39.86	SHT TRM TURN LANE
	5	RT 381+58.68	SHT TRM ARROW
	5	RT 382+35.35	SHT TRM ARROW
	5	RT 383+12.01	SHT TRM ARROW
	5	RT 383+88.63	SHT TRM ARROW
	8	RT 374+00.01 - 379+81.75	SHT TRM SHOULDER DIAGONALS
	11	RT 385+94.39 - 394+05.08	SHT TRM SHOULDER DIAGONALS
		Niabi Zoo Rd	
	58	LT 20+33.40 - 22+08.74	STAGE 1 EDGE LINE
	24	LT 22+08.74	STAGE 1 STOP BAR
	210	LT 15+84.00 - 22+08.74	STAGE 2 RT EDGE LINE
	24	LT 15+84.00	STAGE 2 STOP BAR
	30	RT 22+08.74	STAGE 2 STOP BAR
	332	LT 10+27.51 - 19+81.01	SHT TRM EDGE LINE
	192	RT 10+31.41 - 13+19.88	SHT TRM MEDIAN
	220	CL 13+19.88 - 19+81.01	SHT TRM CENTERLINE
	254	RT 10+31.00 - 15+90.02	SHT TRM EDGE LINE
	144	RT 16+10.25 - 19+81.01	SHT TRM EDGE LINE
	18	LT 10+31.41	SHT TRM STOP BAR
	5	RT 16+16.88	SHT TRM STOP BAR
	6486		

70400100	TEMPORARY CONCRETE BARRIER		NOTE
	FOOT	LOCATION	
	494.0	RT 382+39.38 - 387+33.40	STAGE 1 BARRIER WALL
	191.0	RT 384+84.03 - 386+75.03	STAGE 2 BARRIER WALL
	685.0		

70400200	RELOCATION TEMPORARY CONCRETE BARRIER		NOTE
	FOOT	LOCATION	
	494.0	RT 379+90.00 - 384+84.03	STAGE 2 BARRIER WALL
	494.0		

70600251	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3		NOTE
	EACH	LOCATION	
	1	RT 382+39.38	STAGE 1
	1	RT 387+33.40	STAGE 1
	2		

70600352	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE, NARROW), TEST LEVEL 3		NOTE
	EACH	LOCATION	
	1	RT 379+90.00	STAGE 2
	1	RT 387+75.06	STAGE 2
	2		

78009000	MODIFIED URETHANE MARKING - LETTERS AND SYMBOLS		NOTE
	SQ.FT	LOCATION	
	15.6	RT 381+58.68	RT TURN ARROW - WHITE
	15.6	RT 382+35.35	RT TURN ARROW - WHITE
	15.6	RT 383+12.01	RT TURN ARROW - WHITE
	15.6	RT 383+88.63	RT TURN ARROW - WHITE
	15.6	LT 385+45.08	LT TURN ARROW - WHITE
	15.6	LT 386+20.08	LT TURN ARROW - WHITE
	15.6	LT 386+95.08	LT TURN ARROW - WHITE
	15.6	LT 387+70.08	LT TURN ARROW - WHITE
	125		

78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"		NOTE
	FOOT	LOCATION	
	354	LT 370+45.55 - 374+00.00	EDGE LINE - WHITE
	90	CL 370+45.98 - 374+00.00	CENTERLINE, SKIP DASH - YELLOW
	355	RT 370+45.00 - 374+00.00	EDGE LINE - WHITE
	2,005	LT 374+00.01 - 394+05.08	EDGE LINE - WHITE
	1,014	RT 374+01.01 - 384+15.38	EDGE LINE - WHITE
	765	RT 386+40.14 - 394+05.08	EDGE LINE - WHITE
	50	CL 374+00.01 - 375+73.68	CENTER LINE, SKIP DASH - YELLOW
	15	CL 393+55.08 - 394+05.08	CENTER LINE, SKIP DASH - YELLOW
	3,468	LT & RT 375+73.68 - 384+40.67	MEDIAN - YELLOW
	530	RT 385+25.08 - 387+90.08	MEDIAN - YELLOW
	2,260	LT & RT 387+90.08 - 393+55.08	MEDIAN - YELLOW
	355	LT 394+05.08 - 397+60.41	EDGE LINE - WHITE
	90	CL 394+05.08 - 397+60.24	CENTERLINE, SKIP DASH - YELLOW
	355	RT 394+05.08 - 397+60.08	EDGE LINE - WHITE
		Niabi Zoo Rd Reconstruction	
	1,154	RT 10+31.41 - 13+19.88	MEDIAN - YELLOW
	641	RT 10+31.51 - 15+89.99	EDGE LINE - WHITE
	431	RT 16+10.21 - 19+81.01	EDGE LINE - WHITE
	1,055	LT 10+16.58 - 19+81.01	EDGE LINE - WHITE
	1,322	CL 13+19.88 - 19+81.01	CENTER LINE, DOUBLE YELLOW
	455	CL 19+81.01 - 22+08.74	CENTER LINE, DOUBLE YELLOW
		Resurfacing	
	8,711	CL 10+31.00 - 63+40.00	CENTER LINE, DOUBLE YELLOW
	10,330	LT & RT 10+31.00 - 63+40.00	EDGE LINE - WHITE
	35,805		

78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"		NOTE
	FOOT	LOCATION	
	140	LT 10+18.70 - 10+57.63	ISLAND - WHITE
	140		

78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"		NOTE
	FOOT	LOCATION	
	301	RT 381+38.68 - 384+39.86	TURN LANE - WHITE
	265	LT 385+25.08 - 387+90.08	TURN LANE - WHITE
	566		