

SUMMARY OF QUANTITIES

URBAN

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	0004 90 % FEDERAL 10 % STATE ROCK ISLAND	0004 90 % FEDERAL 10 % STATE HENRY	0011 90 % FEDERAL 10 % STATE EX.SN.081-0005 PR. SN. 081-0194 ROCK ISLAND	0011 90 % FEDERAL 10 % STATE EX.SN.081-0006 PR. SN. 081-0195 ROCK ISLAND
28000305	TEMPORARY DITCH CHECKS	FOOT	120	120			
28000400	PERIMETER EROSION BARRIER	FOOT	1,997	1,997			
28000500	INLET AND PIPE PROTECTION	EACH	2	2			
28100105	STONE RIPRAP, CLASS A3	SQ YD	4,162	187	3,975		
28100109	STONE RIPRAP, CLASS A5	SQ YD	2,469			1,235	1,234
28200200	FILTER FABRIC	SQ YD	2,469			1,235	1,234
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CY YD	445	270	175		
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	8,695	8,695			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	312.6	147.5	165.1		
40600300	AGGREGATE (PRIME COAT)	TON	539	254	285		
40600525	LEVELING BINDER (HAND METHOD), N50	TON	194	85	109		
40600745	POLYMERIZED LEVELING BINDER (HAND METHOD), N90	TON	405	196	209		
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	2,382	2,382			
40600895	CONSTRUCTING TEST STRIP	EACH	2	0.90	1.10		
40600990	TEMPORARY RAMP	SQ YD	532	293	239		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2,570	1,568	1,002		
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	28,948	13,625	15,323		

* Specialty Items
** Non-Participating Items

* 74/280 & 80
** 81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
*** ROCK ISLAND/HENRY COUNTY