

# SUMMARY OF QUANTITIES

*URBAN*

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	0004		0011	
				90 % FEDERAL 10 % STATE ROCK ISLAND	90 % FEDERAL 10 % STATE HENRY	90 % FEDERAL 10 % STATE EX.SN.081-0005 PR. SN. 081-0194 ROCK ISLAND	90 % FEDERAL 10 % STATE EX.SN.081-0006 PR. SN. 081-0195 ROCK ISLAND
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1
50200100	STRUCTURE EXCAVATION	CU YD	497			241	256
50300100	FLOOR DRAINS	EACH	12			6	6
50300225	CONCRETE STRUCTURES	CU YD	367.2			184.2	183.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	656.1			328.1	328.0
50300260	BRIDGE DECK GROOVING	SQ YD	1,608			804	804
50300280	CONCRETE ENCASEMENT	CU YD	8.4			4.2	4.2
50300300	PROTECTIVE COAT	SQ YD	1,924			962	962
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1.0			0.5	0.5
50500505	STUD SHEAR CONNECTORS	EACH	8028			4014	4014
50800105	REINFORCEMENT BARS	POUND	15,230			7615	7615
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	214,320			107,160	107,160
50800515	BAR SPLICERS	EACH	2,102			1,051	1,051
51201400	FURNISHING STEEL PILES HP10X42	FOOT	355			210	145
51202305	DRIVING PILES	FOOT	355			210	145
51203400	TEST PILE STEEL HP10X42	EACH	4			2	2
51204650	PILE SHOES	EACH	24			12	12

\* Specialty Items  
\*\* Non-Participating Items

\* 74/280 & 80  
\*\* (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR  
\*\*\* ROCK ISLAND/HENRY COUNTY

*Rev.*

FILE NAME *	USER NAME * hensonka	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	FAT RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\hensonka\08117984\020	307-shr-500.dgn	DRAWN -	REVISED -			*	**	***	290	9
Default	PLOT SCALE * 100,0000' / 1" =	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
	PLOT DATE * Fri Mar 15 10:41:15 2013	DATE -	REVISED -							
										CONTRACT NO. 64023
										ILLINOIS FED. AID PROJECT