

# SCHEDULE OF QUANTITIES

40600990

## TEMPORARY RAMP – CONTINUED

### West Bound

SQ YD		TOTAL	HENRY LOCATION
RT SIDE	LT SIDE		
13.3	13.3	26.6	W.B. Weigh Scale Entrance Ramp
13.3	13.3	26.6	W.B. I-80 Entrance Ramp
13.3	13.3	26.6	W.B. I-280 Entrance Ramp
13.3	13.3	26.6	W.B. I-80 Entrance Ramp
13.3	13.3	26.6	W.B. I-280 Entrance Ramp
66.5	66.5	133.0	SUB-TOTAL HENRY COUNTY
146.3	146.3	292.6	SUB-TOTAL ROCK ISLAND COUNTY
119.7	119.7	239.4	SUB-TOTAL HENRY COUNTY
266.0	266.0	532.0	TOTAL

42001430

## BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)

E.B. RT SIDE SQ YD	W.B. LT SIDE SQ YD	TOTAL	ROCK ISLAND LOCATION	COMMENTS
	48	48	279 + 12 - 279 + 22	WB WEST OF CREEK
53		53	279 + 14 - 279 + 24	EB WEST OF CREEK
48		48	280 + 99 - 281 + 9	EB EAST OF CREEK
	53	53	281 + 1 - 281 + 11	WB EAST OF CREEK
101	101	202	TOTAL ROCK ISLAND COUNTY	

44000100

## PAVEMENT REMOVAL

E.B. RT SIDE SQ YD	W.B. LT SIDE SQ YD	TOTAL	ROCK ISLAND LOCATION	COMMENTS
	81	81	279 + 12 - 279 + 43	WB WEST OF CREEK
81		81	279 + 14 - 279 + 43	EB WEST OF CREEK
	83	83	280 + 80 - 281 + 11	WB EAST OF CREEK
79		79	280 + 80 - 281 + 9	EB EAST OF CREEK
160	164	324	TOTAL ROCK ISLAND COUNTY	

\* 74/280 & 80  
 \*\* (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR  
 \*\*\* ROCK ISLAND/HENRY COUNTY

FILE NAME =	USER NAME = hensonke	DESIGNED -	REVISED -
ct:\pwork\pwork\hensonke\0117904\0206307-sht-S00.dgn		DRAWN -	REVISED -
Default		CHECKED -	REVISED -
	PLOT DATE = Fri Mar 15 10:49:55 2013	DATE -	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	290	48
CONTRACT NO. 64D23				
ILLINOIS FED. AID PROJECT				