

SCHEDULE OF QUANTITIES

44004250

PAVED SHOULDER REMOVAL

E.B. RT SIDE SQ YD	W.B. LT SIDE SQ YD	TOTAL	ROCK ISLAND LOCATION	COMMENTS
	1294	1294	268 + 00 - 279 + 83	WB NORTH SIDE SHOULDER
	373	373	271 + 77 - 279 + 83	WB SOUTH SIDE SHOULDER
296		296	273 + 60 - 279 + 83	EB NORTH SIDE SHOULDER
1476		1476	266 + 62 - 279 + 83	EB SOUTH SIDE SHOULDER
	1482	1482	280 + 40 - 294 + 38	WB NORTH SIDE SHOULDER
	345	345	280 + 40 - 287 + 96	WB SOUTH SIDE SHOULDER
374		374	280 + 40 - 288 + 52	EB NORTH SIDE SHOULDER
1426		1426	280 + 40 - 293 + 4	EB SOUTH SIDE SHOULDER
3572	3494	7066	TOTAL ROCK ISLAND COUNTY	

48102100

AGGREGATE WEDGE SHOULDER, TYPE B

			<u>East Bound</u>		
<u>Ton</u> RT SIDE	<u>Ton</u> LT SIDE	TOTAL	LOCATION	COMMENTS	
500	500	1,000	This item is a contingency to be used as directed by the Engineer. A quantity of 3600 SQ YD' is estimated.		
10	10	20	380 + 40 - 381 + 40	E.B. TAPER	
644	644	1,288	381 + 40 - 444 + 98	E.B. MAINLINE	
10	10	20	444 + 98 - 445 + 98	E.B. TAPER	
10	10	20	256 + 88 - 257 + 88	E.B. TAPER	
176	176	352	257 + 88 - 275 + 25	E.B. MAINLINE	
40	40	80	285 + 75 - 289 + 73	E.B. MAINLINE	
10	10	20	296 + 42 - 297 + 42	E.B. TAPER	
241	241	482	297 + 42 - 321 + 24	E.B. MAINLINE	
10	10	20	321 + 24 - 322 + 24	E.B. TAPER	
10	10	20	338 + 55 - 339 + 55	E.B. TAPER	
227	227	454	339 + 55 - 361 + 97	E.B. MAINLINE	
10	10	20	361 + 97 - 362 + 97	E.B. TAPER	
10	10	20	367 + 65 - 368 + 65	E.B. TAPER	
462	462	924	368 + 65 - 414 + 31	E.B. MAINLINE	
2,370	2,370	4,740	SUB-TOTAL ROCK ISLAND COUNTY		

48102100

AGGREGATE WEDGE SHOULDER, TYPE B - CONTINUED

			<u>West Bound</u>		
<u>Ton</u> RT SIDE	<u>Ton</u> LT SIDE	TOTAL	LOCATION	COMMENTS	
10	10	20	380 + 40 - 381 + 40	W.B. TAPER	
651	651	1,302	381 + 40 - 445 + 70	W.B. MAINLINE	
10	10	20	445 + 70 - 446 + 70	W.B. TAPER	
10	10	20	254 + 8 - 255 + 8	W.B. TAPER	
204	204	408	255 + 8 - 275 + 25	W.B. MAINLINE	
810	810	1,620	285 + 75 - 365 + 75	W.B. MAINLINE	
10	10	20	365 + 75 - 366 + 75	W.B. TAPER	
10	10	20	371 + 6 - 372 + 6	W.B. TAPER	
107	107	214	372 + 6 - 382 + 64	W.B. MAINLINE	
10	10	20	382 + 64 - 383 + 64	W.B. TAPER	
10	10	20	400 + 73 - 401 + 73	W.B. TAPER	
127	127	254	401 + 73 - 414 + 31	W.B. MAINLINE	
1,969	1,969	3,938	SUB-TOTAL ROCK ISLAND COUNTY		
15	15	30	431 + 95	Median Cross Overs	
15	15	30	271 + 25	Median Cross Overs	
30	30	60	SUB-TOTAL ROCK ISLAND COUNTY		
2370	2370	4740	SUB-TOTAL ROCK ISLAND COUNTY		
1,969	1,969	3,938	SUB-TOTAL ROCK ISLAND COUNTY		
30	30	60	SUB-TOTAL ROCK ISLAND COUNTY		
4369	4369	8738	TOTAL ROCK ISLAND COUNTY		

* 74/280 & 80
 ** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
 *** ROCK ISLAND/HENRY COUNTY

FILE NAME =	USER NAME = hensonke	DESIGNED -	REVISED -
c:\pwork\pwork\hensonke\0117904\0208307-sht-S00.dgn		DRAWN -	REVISED -
Default		CHECKED -	REVISED -
	PLOT DATE = Fri Mar 15 10:50:11 2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

FBI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	290	49
				CONTRACT NO. 64D23
ILLINOIS FED. AID PROJECT				