

SCHEDULE OF QUANTITIES

72700100 STRUCTURAL STEEL SIGN SUPPORT – BREAKAWAY

<u>E.B.</u> <u>POUND</u>	<u>W.B.</u> <u>POUND</u>	<u>TOTAL</u>	<u>ROCK ISLAND</u> <u>LOCATION</u>	<u>COMMENTS</u>
	1395	1395	276 + 00.00 W16X45	LENGTH= 31 FT
	1395	1395	276 + 00.00 W16X45	LENGTH= 31 FT
	1395	1395	276 + 00.00 W16X45	LENGTH= 31 FT
950		950	283 + 25.00 W14X38	LENGTH= 25 FT
1140		1140	283 + 25.00 W14X38	LENGTH= 30 FT
2090	4185	6275	TOTAL ROCK ISLAND COUNTY	

73400100 CONCRETE FOUNDATIONS

<u>E.B.</u> <u>CU YD</u>	<u>W.B.</u> <u>CU YD</u>	<u>TOTAL</u>	<u>ROCK ISLAND</u> <u>LOCATION</u>	<u>COMMENTS</u>
	6.7	6.7	276 + 00.00	3-FOUNDATIONS
4.2		4.2	283 + 25.0	2-FOUNDATIONS
4.2	6.7	10.9	TOTAL ROCK ISLAND COUNTY	

73700100 REMOVE GROUND MOUNTED SIGN SUPPORT

<u>E.B.</u> <u>EACH</u>	<u>W.B.</u> <u>EACH</u>	<u>TOTAL</u>	<u>ROCK ISLAND</u> <u>LOCATION</u>	<u>COMMENTS</u>
	2	2	276 + 00.00	Coal Creek
2		2	283 + 25.0	Coal Creek
2	2	4	TOTAL ROCK ISLAND COUNTY	

* 74/280 & 80
 ** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
 *** ROCK ISLAND/HENRY COUNTY