HMA SCHEDULE – W.B.

HOT–MIX ASPHALT SCHEDULE

LOCATION STATION TO STATION	REMARKS	SURFACE LENGTH FT	SURFACE WIDTH FT	AREA Mainline SQ YD	AREA Shoulder	44000157 HMA SURFACE REMOVAL, 1.75" SQ YD	40600200 BIT. MAT. PRIME COAT (2 APPS.) TON	40600300 AGG. PRIME COAT TON	40603540 POLYM. HMA SURF. MIX "E", N90 (MAINLINE) 1.5" TON	40603570 POLYM. HMA SURF. MIX "E", N90 (MAINLINE) 1.75" TON	40603310 HMA SURF. MIX "C", N50 (SHOULDER) 2" TON	40603310 HMA SURF. MIX "C", N50 (SHOULDER) 1.75" TON	40603310 HMA SURF. MIX "C", N50 (SHOULDER) 1.50" TON	40600745 LEVELING BINDER, N90 Bridge (HM) TON	40600845 LEVELING BINDER, N90 Coal Creek (MM) TON	40600735 POLYMERIZED LEVELING BINDER, N70 (HM) 2–1/4" TON	40603243 POLYMERIZED LEVELING BINDER, N70 TON	40600525 Leveling Binder N50 (HM) TON	48203100 HMA Shoulders (MM) 2–1/4" TON
WEST BOUND MAINLINE	R. I. COUNTY																		
367 65.00 371 6.00	S. CREEK INTSIDE SHLD	341.00	VAR		185.0								15.5						
367 + 64.86 TO 371 + 6.10	MAINLINE	341.24	24 14	910.0	530.8	1,440.8	0.8	1.4		94.8		52.0				1.0		0.6	
371 + 6.10 TO 372 + 6.10	TAPER	100.00	26 12	288.9	133.3	422.2	0.2	0.4	25.8		14.9					0.3	31.9	0.1	
372 + 6.10 TO 382 + 63.99	MAINLINE	1,057.89	26 12	3,056.1	1,410.5	3,056.1	2.6	4.6	272.8		158.0					3.4	385.1	1.6	
382 + 63.99 TO 383 + 63.99	TAPER	100.00	26 12	288.9	133.3	422.2	0.2	0.4	25.8		14.9					0.3	31.9	0.1	
383 + 63.99 TO 400 + 72.69	MAINLINE	1,708.70	24 4	4,556.5	759.4	5,316.0	3.0	6.8		474.4		74.4				5.0		0.8	
383 + 63.99 TO 400 + 72.69	Entrance ramp	1,708.70	VAR 10	2,284.6	1,898.6	4,183.2	2.4	3.4		237.9		186.1				2.5		2.1	
393 + 21.03 TO 400 + 72.69	Gore Area	751.66	VAR	1,080.8	0.0	1,080.8	0.6	1.6		112.5		0.0				1.2		0.0	
400 + 72.69 TO 401 + 72.69	TAPER	100.00	26 12	288.9	133.3	422.2	0.2	0.4	25.8		14.9	13.1				0.3	31.9	0.1	
401 + 72.69 TO 414 + 31.11	MAINLINE	1,258.42	26 12	2,437.0	1,677.9	2,437.0	2.4	3.7	217.5		187.9	164.4				2.7	307.1	1.8	
EMERGENCY MEDIAN CROSSOVERS	R. I. COUNTY																		
431 + 95.00	MEDIAN			238.1			0.1	0.4	21.3			0.0							
271 + 25.07	MEDIAN			238.1			0.1	0.4	21.3			0.0							
SUB TOTAL WEST BOUND	R.I. COUNTY			89771.9	45140.1	114256.1	75.0	127.8	5156.3	3125.7	2906.5	1496.9	338.0	2.5	1125.0	95.7	6901.7	43.4	0.0

* 74/280 & 80
** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
*** ROCK ISLAND/HENRY COUNTY

FILE NAME =	USER NAME = hensonke	DESIGNED -	REVISED -
c:\pw_work\pwidot\hensonke\d0117904\D204307-sht-S00.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = Fri Mar 15 11:24:32 2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HMA SCHEDULE – W.B.

SCALE: SHEET OF SHEETS STA. TO STA.

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	290	91

CONTRACT NO. 64D23

ILLINOIS FED. AID PROJECT