HMA SCHEDULE – W.B.

HOT–MIX ASPHALT SCHEDULE

LOCATION STATION TO STATION	REMARKS	SURFACE LENGTH FT	SURFACE WIDTH M FT	SURFACE WIDTH S FT	AREA Mainline SQ YD	AREA Shoulder SQ YD	44000156 HMA SURFACE REMOVAL, 1.75" SQ YD	40600200 BIT. MAT. PRIME COAT (2 APPS.) TON	40600300 AGG. PRIME COAT TON	40603570 POLYM. HMA SURF. MIX "E", N90 (MAINLINE) 1.5" TON	40603570 POLYM. HMA SURF. MIX "E", N90 (MAINLINE) 1.75" TON	40603310 HMA SURF. MIX "C", N50 (SHOULDER) 2" TON	40603310 HMA SURF. MIX "C", N50 (SHOULDER) 1.75" TON	40603310 HMA SURF. MIX "C", N50 (SHOULDER) 1.50" TON	40600745 LEVELING BINDER, N90 Bridge (HM) TON	40600845 LEVELING BINDER, N90 Coal Creek (MM) TON	40600745 POLYMERIZED BINDER, N90 (MAINLINE) (HM) TON	40603243 POLYMERIZED BINDER, N90 (MAINLINE) (MM) 2–1/4" TON	40600525 Leveling Binder N50 (HM) TON	48203100 HMA Shoulders (MM) 2–1/4" TON
WEST BOUND MAINLINE	HENRY COUNTY																			
571 + 19.88 TO 574 + 21.04	Entrance Ramp	301.16	VAR	10	556.6	334.6	891.2	0.5	0.8		58.0		32.8				0.6		0.4	
571 + 31.99 TO 573 + 32.16	Entrance Ramp taper area	130.00	VAR		66.7		66.7	0.0	0.1		6.9		0.0				0.1		0.0	
573 + 32.16 TO 574 + 21.04	GORE AREA	88.89		VAR	0.0	129.3	129.3	0.1	0.0		13.5		12.7				0.0		0.1	
574 + 21.04 TO 585 + 58.44	MAINLINE	1,137.40	24	14	3,033.1	1,769.3	4,802.3	2.7	4.5		315.8		173.4				3.3		1.9	
585 + 58.44 TO 599 + 64.46	MAINLINE	1,406.02	24	5	3,749.4	781.1	4,530.5	2.6	5.6		390.4		76.5				4.1		0.9	
EMERGENCY MEDIAN CROSSOVERS	HENRY COUNTY																			
445 + 6.38	MEDIAN				238.1		238.1	0.1	0.4	21.3							0.3	33.3	0.0	0.0
571 + 45.71	MEDIAN				238.1			0.1	0.4	21.3							0.3	33.3	0.0	0.0
690 + 14.36	MEDIAN				238.1		238.1	0.1	0.4	21.3							0.3	33.3	0.0	0.0
SUB TOTAL WEST BOUND	HENRY COUNTY				96139.6	52605.7	75341.0	84.1	144.2	5401.4	4116.9	933.4	1983.9	2189.8	0.0	0.0	105.8	7306.7	56.0	2884.7
SUB TOTAL	R. I. COUNTY						213624	147.5	254	10151	6331	5681	2668	800	5.0	2382.0	191	13625	85	0
SUB TOTAL	HENRY COUNTY						136837	165.1	285	11356	7342	1959	3328	4637	0.0	0.0	209	15323	109	6105
	SUB TOTAL						350461	312.6	539	21507	13673	7640	5996	5437	5	2382	400	28948	194	6105
	GRAND TOTAL						350461	312.6	539	35180		19073			5	2382	400	28948	194	6105

* 74/280 & 80
** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
*** ROCK ISLAND/HENRY COUNTY

FILE NAME = c:\pw_work\pwidot\hensonke\d0117904\D204307-sht-S00.dgn	USER NAME = hensonke	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = Fri Mar 15 11:25:07 2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HMA SCHEDULE – W.B.

SCALE: | SHEET OF SHEETS | STA. TO STA.

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	290	93

CONTRACT NO. 64D23

ILLINOIS FED. AID PROJECT