

STRIPING SCHEDULE – E.B.

STRIPING SCHEDULE																		
LOCATION		STATION TO STATION		REMARKS		LENGTH FT	78009004		78009006	7800908	78009012		SHORT TERM APP. Rate	70300100				
							MODIFIED URETHANE PAVEMENT MARKING – LINE 4"		MODIFIED URETHANE PAVEMENT MARKING – LINE 6"	MODIFIED URETHANE PAVEMENT MARKING – LINE 8"	MODIFIED URETHANE PAVEMENT MARKING – LINE 12"	MODIFIED URETHANE PAVEMENT MARKING – LINE 12"		SHORT-TERM PAVEMENT MARKING Note Center line short term will be placed like permenate pavement marking				
							EDGE LINES		CL		CHEVRON	DIAGONAL		PHASE	PHASE	White	Yellow	White
							White	Yellow	White	White	White	White		1	2	FOOT	DIAGONALS	DIAGONALS
														FOOT	FOOT	FOOT		
EAST BOUND MAINLINE				R. I. COUNTY														
354	+	89.77	TO	360	+	68.87	MAINLINE	579	579	579	150		2		300	48	48	
360	+	68.87	TO	361	+	86.97	BRIDGE OMISSION	118	118	118	30							
361	+	86.97	TO	380	+	40.30	MAINLINE	1,853	1,853	1,853	470		2		940	152	152	
380	+	40.30	TO	445	+	97.69	MAINLINE	6,557	6,557	6,557	1,640		3		4,920	528	528	
445	+	97.69	TO	452	+	89.89	EXIT RAMP	692	692				2		1,384		56	
450	+	26.35	TO	452	+	89.89	EXIT RAMP	264			530	138	2		1,336			
445	+	97.69	TO	452	+	89.89	MAINLINE	692		692	180		2		360	56		
452	+	89.89	TO	461	+	29.88	MAINLINE	840	840	840	210		2		420	72	72	
461	+	29.88	TO	464	+	95.93	MAINLINE	366		366	100		2		200	32		
461	+	29.89	TO	461	+	93.89	ENTRANCE RAMP	64					2		256			
461	+	29.89	TO	464	+	95.93	ENTRANCE RAMP	366	366				2		732		32	
461	+	93.89	TO	463	+	93.89	ENTRANCE RAMP	200			400		2		800			
463	+	93.89	TO	464	+	95.93	ENTRANCE RAMP	102			30		2		60		16	
464	+	95.93	TO	238	+	12.80	Sta. Equa.											
238	+	12.80	TO	244	+	28.53	MAINLINE	616		616	160		2		320	56		
238	+	12.80	TO	240	+	00	EXIT RAMP	187			50		2		100		16	
238	+	12.80	TO	242	+	7.87	EXIT RAMP	395	395				2		790		32	
240	+	00	TO	240	+	65.11	EXIT RAMP	65			65		2		130			
240	+	65.11	TO	242	+	7.87	EXIT RAMP	143			290	69	2		718			
242	+	7.87	TO	244	+	28.53	EXIT RAMP	221	442				2		1,011			
244	+	28.53	TO	246	+	72.09	MAINLINE	244	244	244	70		2		140	36	36	
246	+	72.09	TO	256	+	87.51	MAINLINE	1,015		1,015	260		2		520	132		
246	+	72.09	TO	248	+	76.98	ENTRANCE RAMP	205	205		410		2		1,230		24	
248	+	76.98	TO	251	+	16.98	ENTRANCE RAMP	240	240		70		2		620		24	
251	+	16.98	TO	256	+	87.51	ENTRANCE RAMP	571	571				2		1,141		48	
256	+	87.51	TO	275	+	25.00	MAINLINE	1,837	1,837	1,837	460		3		1,380	152	152	
256	+	62.00	TO	286	+	00	PHASE 1	2,938	2,938				2	589			240	
273	+	70.78	TO	288	+	52.00	PHASE 1	1,481	1,481				2	300			120	
256	+	61.56	TO	286	+	2.80	PHASE 2						2		591			
271	+	61.56	TO	293	+	4.00	PHASE 2						2		434			
275	+	25.00	TO	279	+	13.81	COAL CREEK	389	389	389	100				80	32	32	
279	+	13.81	TO	281	+	9.07	BRIDGE OMISSION	195.26	195	195	195	50						

* 74/280 & 80
 ** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
 *** ROCK ISLAND/HENRY COUNTY