

STRIPING SCHEDULE – W.B.

STRIPING SCHEDULE																		
LOCATION				78009004		78009006	7800908	78009012			70300100							
STATION TO STATION				REMARKS		LENGTH FT	MODIFIED URETHANE PAVEMENT MARKING – LINE 4"		MODIFIED URETHANE PAVEMENT MARKING – LINE 6"	MODIFIED URETHANE PAVEMENT MARKING – LINE 8"	MODIFIED URETHANE PAVEMENT MARKING – LINE 12"	MODIFIED URETHANE PAVEMENT MARKING – LINE 12"	SHORT TERM APP. Rate	SHORT-TERM PAVEMENT MARKING will be placed like permenate pavement marking Note Center line short term				
							EDGE LINES		CL		CHEVRON	DIAGONAL	PHASE	PHASE	White	Yellow	White	
				White	Yellow	White	White	White	White	White	1	2	FOOT	DIAGONALS	DIAGONALS			
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT			
WEST BOUND MAINLINE				R. I. COUNTY														
285	+	75.00	TO	366	+	75.28	MAINLINE	8,100.28	8,100	8,100	2,030			3		6,090	656	656
366	+	75.28	TO	367	+	64.86	BRIDGE OMISSION	89.58	90	90	30							
367	+	64.86	TO	371	+	35.05	MAINLINE	370.19	370	370	100			2		200	32	32
371	+	35.05	TO	383	+	63.99	MAINLINE	1,228.94	1,229	1,229	310			3		930	104	104
383	+	63.99	TO	400	+	72.69	MAINLINE	1,708.70		1,709	430			2		860	144	144
383	+	63.99	TO	389	+	60.99	ENTRANCE RAMP	597.00	597					2		1,194		48
389	+	60.99	TO	393	+	20.99	ENTRANCE RAMP	360.00	360		90			2		900		32
393	+	20.99	TO	397	+	80.69	ENTRANCE RAMP	459.70	460		920			2		2,759		40
397	+	80.69	TO	400	+	72.69	ENTRANCE RAMP	292.00	292	292				2		1,732		24
400	+	72.69	TO	414	+	31.11	MAINLINE	1,358.42	1,358	1,358	340			3		1,020	112	112
SUB TOTAL WEST BOUND				R.I. COUNTY														
				29,113	29,512	7,660	3,016	156	65	905	935	36,376	2,384	2,512				

* 74/280 & 80
 ** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
 *** ROCK ISLAND/HENRY COUNTY