

STRIPING SCHEDULE – W.B.

STRIPING SCHEDULE															
LOCATION				70300220		78300100	70301000	X7830070	X7830074	X7830076	X7830078				
STATION TO STATION				REMARKS		LENGTH FT	TEMPORARY PAVEMENT MARKING LINE – 4"		PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	GROOVING FOR RECESSED PAVEMENT MARKING 5" LINE	GROOVING FOR RECESSED PAVEMENT MARKING 7" LINE CL	GROOVING FOR RECESSED PAVEMENT MARKING 9" LINE	GROOVING FOR RECESSED PAVEMENT MARKING 13" LINE	
							PHASE 1	PHASE 2							SQ FT
WEST BOUND MAINLINE				HENRY COUNTY											
571	+	32.09	TO	573	+	32.09	ENTRANCE RAMP	200.00			203	200		400	
573	+	32.09	TO	574	+	21.04	ENTRANCE RAMP	88.95			91	89		180	
574	+	21.04	TO	585	+	58.44	MAINLINE	1,137.40			129	2,275	290		
585	+	58.44	TO	599	+	64.94	MAINLINE	1,406.50			160	1,407	360		
585	+	58.44	TO	591	+	9.59	EXIT RAMP	551.15			430	1,110		157	
591	+	9.59	TO	593	+	65.99	EXIT RAMP	256.40			294	256		520	
593	+	65.99	TO	599	+	64.94	EXIT RAMP	598.95			258	599	150		
SUB TOTAL EAST BOUND				HENRY COUNTY				0	0	540	6,422	68,800	8,890	2,430	668
				Total Rock Island County				8,976	9,799	305	11,360	115,262	14,920	6,869	713
				Total Henry County				0	0	1,109	12,147	137,264	17,660	4,598	1,007
				Sub Total				8,976	9,799	1,414	23,507	252,526	32,580	11,467	1,720
				Grand Total				18,775		1,414	23,507	252,526	32,580	11,467	1,720

* 74/280 & 80
 ** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
 *** ROCK ISLAND/HENRY COUNTY

FILE NAME =	USER NAME = hensonke	DESIGNED -	REVISED -
ct:\pw\work\p\dot\hensonke\0117904\0206307-sht-S00.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = Fri Mar 15 11:16:55 2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

STRIPING SCHEDULE – W.B.

SCALE: SHEET OF SHEETS STA. TO STA.

FBI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	290	107
CONTRACT NO. 64D23				
ILLINOIS FED. AID PROJECT				