PATCHING SCHEDULE – W.B.

12 FEET LANE WIDTH				CLASS B PATCHES 44200970		44200974		44200976		44213200	44201299	44213204	42001200	40601005
STATION	REMARKS	PATCH		TYPE 2		TYPE 3		TYPE 4		SAWING	DOWEL BARS	TIE BARS	PAVEMENT FABRIC	HMA REPLACEMENT OVER PATCHES
		LT LANE (feet)	RT LANE (feet)	LT LANE (yd*)	RT LANE (yd*)	LT LANE (yd*)	RT LANE (yd*)	LT LANE (yd*)	RT LANE (yd*)	(3W+?L) (feet)	(each)	(each)	(yd*)	TONS
371 + 68	W.B.		12				16.0			60	20		16.0	3.1
372 + 46	W.B.		8		10.7					52	20			2.1
374 + 24	W.B.	6	6	8.0	8.0					90	40			3.1
376 + 26	W.B.		6		8.0					48	20			1.6
377 + 27	W.B.		6		8.0					48	20			1.6
378 + 26	W.B.	6	6	8.0	8.0					90	40			3.1
379 + 27	W.B.		6		8.0					48	20			1.6
381 + 27	W.B.		6		8.0					48	20			1.6
383 + 27	W.B.		6		8.0					48	20			1.6
384 + 28	W.B.		6		8.0					48	20			1.6
386 + 28	W.B.		6		8.0					48	20			1.6
396 + 30	W.B.	6	6	8.0	8.0					90	40			3.1
397 + 32	W.B.	6	6	8.0	8.0					90	40			3.1
398 + 73	W.B.		8		10.7					52	20			2.1
399 + 33	W.B.		6		8.0					48	20			1.6
400 + 33	W.B.	6		8.0						48	20			1.6
402 + 34	W.B.		6		8.0					48	20			1.6
403 + 34	W.B.	6		8.0						48	20			1.6
404 + 34	W.B.		6		8.0					48	20			1.6
406 + 34	W.B.	6	6	8.0	8.0					90	40			3.1
408 + 32	W.B.		6		8.0					48	20			1.6
410 + 32	W.B.	6	6	8.0	8.0					90	40			3.1
412 + 39	W.B.		6		8.0					48	20			1.6
412 + 84	W.B.	12				16.0				60	20		16.0	3.1
413 + 12	W.B.	6	6	8.0	8.0					90	40			3.1
413 + 76	W.B.	6	6	8.0	8.0					90	40			3.1
	W.B. Rock Island Sub–total			645	1376	16	80	0	0	11990	5100	0	96	415

* 74/280 & 80
** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
*** ROCK ISLAND/HENRY COUNTY

FILE NAME = c:\pw_work\pwidot\hensonke\d0117904\D204307-sht-S00.dgn	USER NAME = hensonke	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = Fri Mar 15 11:11:20 2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE – W.B.

SCALE: | SHEET OF SHEETS | STA. TO STA.

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	290	137

CONTRACT NO. 64D23

ILLINOIS FED. AID PROJECT