

PATCHING SCHEDULE – W.B.

12 FEET LANE WIDTH		CLASS B PATCHES										SAWING (3W + ?L) (feet)	DOWEL BARS (each)	TIE BARS (each)	PAVEMENT FABRIC (yd*)	HMA REPLACEMENT OVER PATCHES TONS				
		44200970		44200974		44200976		44213200		44213204							42001200		40601005	
		PATCH		TYPE 2		TYPE 3		TYPE 4												
STATION	REMARKS	LT LANE (feet)	RT LANE (feet)	LT LANE (yd*)	RT LANE (yd*)	LT LANE (yd*)	RT LANE (yd*)	LT LANE (yd*)	RT LANE (yd*)											
595 + 73	W.B.		6		8.0							48	20			1.6				
595 + 91	W.B.	6	6	8.0	8.0							90	40			3.1				
597 + 92	W.B.	6	6	8.0	8.0							90	40			3.1				
598 + 93	W.B.	6	6	8.0	8.0							90	40			3.1				
W.B. Henry Sub-total				624	1147	21	37	0	100			10532	4400	84	159	378				

ROCK ISLAND TOTAL	2843	4307	189	437	0	223	41542	17460	157	849	1568
HENRY TOTAL	1203	3029	59	309	27	487	26102	10620	380	881	1002
GRAND TOTAL	11382		994		737		67644	28080	537	1731	2570

* 74/280 & 80
 ** (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR
 *** ROCK ISLAND/HENRY COUNTY

FILE NAME =	USER NAME = hensonke	DESIGNED -	REVISED -
c:\pwork\pwork\hensonke\0117904\0206307-shr-S00.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = Fri Mar 15 11:13:02 2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PATCHING SCHEDULE – W.B.

SCALE: SHEET OF SHEETS STA. TO STA.

FBI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	290	144
CONTRACT NO. 64D23				
ILLINOIS FED. AID PROJECT				