

SCHEDULE OF QUANTITIES

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

FOOT	LOCATION
	IL 84
12.0	Sta 1481 + 92 Stages I and II
12.0	Sta 1487 + 78 Stages I and II
12.0	Sta 1490 + 52 Stages III and IV
12.0	Sta 1497 + 32 Stages III and IV
<u>48.0</u>	TOTAL

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
	IL 84
21.3	Sta 1481 + 75 - 1497 + 75 White Shoulder LT
21.3	Sta 1481 + 75 - 1497 + 75 White Shoulder RT
53.3	Sta 1481 + 75 - 1497 + 75 Yellow Centerline
112.0	Sta 1483 + 28 - 1486 + 59 Stage I RT
171.3	Sta 1482 + 57 - 1487 + 68 Stage I LT
144.7	Sta 1482 + 87 - 1487 + 18 Stage II RT
94.3	Sta 1483 + 53 - 1486 + 39 Stage II LT
117.7	Sta 1492 + 10 - 1495 + 60 Stage III RT
204.3	Sta 1491 + 12 - 1497 + 22 Stage III LT
172.7	Sta 1491 + 44 - 1496 + 59 Stage IV RT
102.7	Sta 1492 + 45 - 1495 + 50 Stage IV LT
24.0	Sta 1481 + 92 Stages I and II
24.0	Sta 1487 + 78 Stages I and II
24.0	Sta 1490 + 52 Stages III and IV
24.0	Sta 1497 + 32 Stages III and IV
<u>1,311.6</u>	TOTAL

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
	IL 84
275.0	Sta 1483 + 67 - 1486 + 34 Stage I
<u>337.5</u>	Sta 1492 + 36 - 1495 + 71 Stage III
612.5	TOTAL

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
	IL 84
275.0	Sta 1483 + 70 - 1486 + 35 Stage II
<u>262.5</u>	Sta 1492 + 80 - 1495 + 38 Stage IV
537.5	TOTAL

70600250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
	IL 84
1.0	Sta 1483 + 54 Stage I
1.0	Sta 1486 + 47 Stage I
1.0	Sta 1492 + 23 Stage III
1.0	Sta 1495 + 85 Stage III
<u>4.0</u>	TOTAL

70600350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
	IL 84
1.0	Sta 1483 + 57 Stage II
1.0	Sta 1486 + 48 Stage II
1.0	Sta 1492 + 66 Stage IV
1.0	Sta 1495 + 52 Stage IV
<u>4.0</u>	TOTAL

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
	IL 84
1,600.0	Sta 1481 + 75 - 1497 + 75 White Shoulder LT
1,600.0	Sta 1481 + 75 - 1497 + 75 White Shoulder RT
1,600.0	Sta 1481 + 75 - 1497 + 75 Yellow Centerline LT
1,600.0	Sta 1481 + 75 - 1497 + 75 Yellow Centerline RT
<u>6,400.0</u>	TOTAL

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
	IL 84
<u>20.0</u>	Sta 1481 + 75 - 1497 + 75 @ 80'-0"
20.0	TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
	IL 84
114.6	Sta 1481 + 92 - 1483 + 64 Stage I CL
92.6	Sta 1486 + 41 - 1487 + 80 Stage I CL
221.8	Sta 1483 + 27 - 1486 + 60 Stage I RT
192.5	Sta 1483 + 51 - 1486 + 40 Stage I LT
133.2	Sta 1490 + 52 - 1492 + 52 Stage III CL
123.9	Sta 1495 + 46 - 1497 + 32 Stage III CL
233.1	Sta 1492 + 11 - 1495 + 61 Stage III RT
<u>203.1</u>	Sta 1492 + 45 - 1495 + 50 Stage III LT
1,314.8	TOTAL

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
	IL 84
<u>20.0</u>	Sta 1481 + 75 - 1497 + 75
20.0	TOTAL

Z0025505 PROPERTY MARKERS

EACH	LOCATION
	IL 84
<u>10.0</u>	As Needed & Directed by the Resident Engineer
10.0	TOTAL