

MAINLINE SCHEDULE													
STA. TO STA.		LENGTH	WIDTH	HMA SURF CSE	POLY LEVEL BINDER (MM)	LEVEL BINDER (HM)	HMA SURF REM 2 1/4"	HMA SURF REM VARIABLE DEPTH	MIX FOR JTS, CRACKS & FLGWYS	BIT. MAT'L (PR CT)	AGG. (PR CT)	AGG SHLD TY B	TEMP RAMP
1034+58	1154+50	1192	27	3022.0	1511.0	18.0	35976.0		10.8	4676.9	72.0	682.9	18.0
1154+50	1174+14	1964	29	531.6	265.8	3.2	6328.4		1.9	822.7	12.7	111.8	
1174+14	1179+12	498	26	120.8	60.4	0.7	1438.7		0.4	187.0	2.9	28.4	
1179+12	1191+44	1232	29	333.5	166.8	2.0	3969.8		1.2	516.1	7.9	70.2	
1191+44	1216+35	2491	26	604.5	302.3	3.6	7196.2		2.2	935.5	14.4	141.8	
1216+35	1236+48	2013	29	544.9	272.5	3.2	6486.3		1.9	843.2	13.0	114.6	
1236+48	1240+47	399	26	96.8	48.4	0.6	1152.7		0.3	149.8	2.3	22.7	
1240+47	1411+00	17053	29	4615.7	2307.9	27.5	54948.6		16.5	7143.3	109.9	971.1	
1411+00	1421+00	1000	32	298.7	149.4	1.8	3555.6		1.1	462.2	7.1		
1421+00	1425+50	450	39	163.8	50.4	0.6	1200.0	750.0	0.4	156.0	2.4		
1425+50	1431+50	600	39	224.0	64.4	0.8	1533.3	1066.7	0.5	199.3	3.1		
1431+50	1439+20	770	48.5	355.7	82.6	1.0	1967.8	2181.7	0.6	255.8	3.9		
1439+68	1458+78	1910	39	713.1	205.0	2.4	4881.1	3395.6	1.5	634.5	9.8		18.0
TOTALS				11974	5651	65	130634	7394	39	16982	261	2144	36

PAVEMENT MARKING SCHEDULE																					
LOCATION		PAINT	PAINT	PAINT	THERM	THERM	THERM	THERM	THERM	THERM	THERM	THERM	THERM	TEMP	TEMP	TEMP	TEMP	TEMP	TEMP	SHORT-	WORK
		4"(3)	4"(3)	6"(3)	4"	4"	6"	6"	8"	12"	12"	24"	LTR. & SYM.	MARK	MARK	MARK	MARK	MARK	LTR. & SYM.	TERM	ZONE PAVT
STA		WHITE	YELLOW	YELL	WHITE	YELL	YELL	WHITE	WHITE	WHITE	YELL	WHITE	SQ. FT.	4"	6"	8"	12"	24"	SQ. FT.	MARK	MARK REM
FOOT		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
BUREAU COUNTY																					
1034+93	TO	1153+50			47428.0		5928.5								71142.0	8892.9				3557.1	391.3
1153+50	TO	1421+00 (2)			107000.0		10680.0								160500.0	16020.0				8025.0	882.8
1421+00	TO	1458+78						944.5								2833.5				1133.4	124.7
IL 40 INTERSECTION (STA 1153+50)																					
RR CROSSING (STA 1439+44)																					
PARKING STRIPING (STA TO STA)																					
CROSSWALKS (STA 1432+00)																					
NO PASSING ZONES (1)																					
RT STA 1037+75 - 1045+20 (SOLID YELLOW)																					
LT STA 1046+75 - 1054+15 (SOLID YELLOW)																					
RT STA 1083+70 - 1092+70 (SOLID YELLOW)																					
LT STA 1094+80 - 1106+40 (SOLID YELLOW)																					
RT STA 1124+90 - 1132+30 (SOLID YELLOW)																					
LT & RT STA 1132+30 - 1136+50 (SOLID YELLOW)																					
LT STA 1136+50 - 1147+10 (SOLID YELLOW)																					
RT STA 1158+10 - 1166+60 (SOLID YELLOW)																					
CENTERLINE STA 1166+60 - 1180+32.8 (DOUBLE YELLOW)																					
LT STA 1180+32.8 - 1190+36 (SOLID YELLOW)																					
RT STA 1208+31.2 - 1218+34.4 (SOLID YELLOW)																					
CENTERLINE STA 1218+34.4 - 1220+45.6 (DOUBLE YELLOW)																					
LT STA 1220+45.6 - 1229+96 (SOLID YELLOW)																					
RT STA 1231+54.4 - 1241+04.8 (SOLID YELLOW)																					
CENTERLINE STA 1241+04.8 - 1264+80.8 (DOUBLE YELLOW)																					
LT STA 1264+80.8 - 1274+84 (SOLID YELLOW)																					
RT STA 1280+64.8 - 1290+15.2 (SOLID YELLOW)																					
LT STA 1291+20.8 - 1300+71.2 (SOLID YELLOW)																					
LT STA 1349+66 - 1354+56.8 (SOLID YELLOW)																					
RT STA 1368+82.4 - 1375+68.8 (SOLID YELLOW)																					
LT STA 1376+74.4 - 1381+49.6 (SOLID YELLOW)																					
GRAND TOTAL		154428	41776	16609	943	221	945	97	400	342	168	154	324	297798	28037	1200	1530	462	972	12716	1399

- (1) R.E. TO VERIFY NO PASSING ZONES PRIOR TO MILLING OPERATION
- (2) CENTERLINE QUANTITIES SUBTRACTED IN THIS ROW WHERE THERE ARE DOUBLE YELLOW LINES.
- (3) PAINT PVT MARKING QUANTITIES ARE DOUBLED TO ACCOUNT FOR TWO APPLICATIONS-SEE SP PROVISIONS
- (4) TEMPORARY PAVEMENT MARKINGS TO BE PLACED ON THE MILLED SURFACE AND LEVELING BINDER. PLACE ON SURFACE COURSE IF NEEDED

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	Schedule of Quantities	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILE#		DRAWN -	REVISED -			613	(8C,9,10,11) RS-3	BUREAU	18	9
	PLOT SCALE = *SCALE*	CHECKED -	REVISED -			CONTRACT NO. 66919				
	PLOT DATE = *DATE*	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT		