

82

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY	ROADWAY	STRUCTURAL
				0004		0040
				80/20	100% STATE FUNDS	80/20
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25		
20200100	EARTH EXCAVATION	CU YD	20	20		
20300100	CHANNEL EXCAVATION	CU YD	786	786		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	342	342		
* 25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23		
* 25100115	MULCH, METHOD 2	ACRE	0.25	0.25		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100		
28000400	PERIMETER EROSION BARRIER	FOOT	724	724		
28100707	STONE DUMPED RIPRAP, CLASS A4	SO YD	515			515
28200200	FILTER FABRIC	SO YD	515			515
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SO YD	350	350		

*SPECIALTY ITEM



USER NAME : Plotted by Roadway7	DESIGNED - RWK	REVISED -
	DRAWN - RWK	REVISED -
PLOT SCALE = 2.0000' / 1"	CHECKED - ST	REVISED -
PLOT DATE	DATE - 11/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
IL ROUTE 116			
SCALE: N/A	SHEET NO. 1 OF 6 SHEETS	STA.	TO STA.

F.A.P. RTE. 665	SECTION 1144-B-1BR	COUNTY FULTON	TOTAL SHEETS 48	SHEET NO. 3
CONTRACT NO. 68778				
ILLINOIS FED. AID PROJECT				