

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY	ROADWAY	STRUCTURAL
				0004		0040
80/20	100% STATE FUNDS	80/20				
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	10	10		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	145	145		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	147	147		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	41	41		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	45	45		
44000100	PAVEMENT REMOVAL	SQ YD	242	242		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	489	489		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	172	172		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1
50200100	STRUCTURE EXCAVATION	CU YD	165			165
50300225	CONCRETE STRUCTURES	CU YD	53.3			53.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	179.4			179.4
50300260	BRIDGE DECK GROOVING	SQ YD	360			360
50300280	CONCRETE ENCASEMENT	CU YD	4.2			4.2



USER NAME : Plotted by Roadways7
 DESIGNED - RWK
 DRAWN - RWK
 CHECKED - ST
 DATE - 11/2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 IL ROUTE 116
 SCALE: N/A SHEET NO. 2 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
665	144-B-118R	FULTON	48	4
CONTRACT NO. 68778				
ILLINOIS FED. AID PROJECT				

141