

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY	ROADWAY	STRUCTURAL
				0004		0040
80/20	100% STATE FUNDS	80/20				
50300300	PROTECTIVE COAT	SQ YD	457			457
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1
50500505	STUD SHEAR CONNECTORS	EACH	1080			1080
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	47930			47930
50800515	BAR SPLICERS	EACH	483			483
51201400	FURNISHING STEEL PILES HP10x42	FOOT	150			150
51202305	DRIVING PILES	FOOT	150			150
51203400	TEST PILE STEEL HP10x42	EACH	2			2
51204650	PILE SHOES	EACH	12			12
51500100	NAME PLATES	EACH	1			1
52100520	ANCHOR BOLTS, 1"	EACH	24			24
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	64			64
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	50	50		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		

\* SPECIALTY ITEM



USER NAME : Plotted by Roadways?  
 CONSULTING ENGINEERS  
 Springfield, Illinois  
 PLOT SCALE : 2,0000 1/1 in.  
 PLOT DATE :

DESIGNED - RWK  
 DRAWN - RWK  
 CHECKED - ST  
 DATE - 11/2012

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 IL ROUTE 116

SCALE: N/A SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A.P. REL. 665	SECTION (144-B-1)BR	COUNTY FULTON	TOTAL SHEETS 48	SHEET NO. 5
CONTRACT NO. 68778				
ILLINOIS FED. AID PROJECT				