

## SCHEDULE OF QUANTITIES

### CLASS A PATCHING, 10" (CONT'D)

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200549	44200553	44200557	44200559	44213000	44213200	44213204
					TYPE I 10.0" (sq. yd)	TYPE II 10.0" (sq. yd)	TYPE III 10.0" (sq. yd)	TYPE IV 10.0" (sq. yd)	PATCHING REINFORCEMENT (sq. yd)	SAW CUTS (ft)	TIE BARS 3/4" (each)
281+10	NB	DL	6.00	6.00	4.00				4.00	42.0	
281+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
282+50	NB	DL	8.00	12.00		10.67			10.67	72.0	
282+75	NB	DL	6.00	6.00	4.00				4.00	42.0	
286+75	NB	DL	10.00	6.00		6.67			6.67	54.0	
287+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
287+90	NB	DL	6.00	6.00	4.00				4.00	42.0	
288+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
288+60	NB	DL	20.00	12.00				26.67	26.67	108.0	22
288+80	NB	DL	30.00	12.00				40.00	40.00	138.0	32
289+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
290+00	NB	DL	20.00	6.00		13.33			13.33	84.0	22
297+00	NB	DL	8.00	12.00		10.67			10.67	72.0	
297+50	NB	DL	15.00	6.00		10.00			10.00	69.0	
298+50	NB	DL	12.00	6.00		8.00			8.00	60.0	
299+00	NB	DL	6.00	12.00		8.00			8.00	66.0	
299+25	NB	DL	6.00	6.00	4.00				4.00	42.0	
299+50	NB	DL	30.00	6.00			20.00		20.00	114.0	32
300+00	NB	DL	40.00	6.00				26.67	26.67	144.0	42
300+50	NB	DL	12.00	12.00			16.00		16.00	84.0	
302+50	NB	DL	20.00	12.00				26.67	26.67	108.0	22
302+75	NB	DL	6.00	6.00	4.00				4.00	42.0	
303+00	NB	DL	12.00	12.00			16.00		16.00	84.0	
313+25	NB	DL	6.00	6.00	4.00				4.00	42.0	
318+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
321+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
322+00	NB	DL	25.00	6.00			16.67		16.67	99.0	28
328+50	NB	DL	10.00	12.00		13.33			13.33	78.0	
331+20	NB	DL	6.00	6.00	4.00				4.00	42.0	
333+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
333+25	NB	DL	6.00	6.00	4.00				4.00	42.0	
SUB-TOTAL =					60.0	80.7	68.7	120.0	329.3	2064.0	200

\*LONGITUDINAL BARS ARE #7