

SCHEDULE OF QUANTITIES

CLASS A PATCHING, 10" (CONT'D)

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200549 TYPE I 10.0" (sq. yd)	44200553 TYPE II 10.0" (sq. yd)	44200557 TYPE III 10.0" (sq. yd)	44200559 TYPE IV 10.0" (sq. yd)	44213000 PATCHING REINFORCEMENT (sq. yd)	44213200 SAW CUTS (ft)	44213204 TIE BARS 3/4" (each)
333+40	NB	DL	6.00	6.00	4.00				4.00	42.0	
333+75	NB	DL	25.00	6.00			16.67		16.67	99.0	28
334+75	NB	DL	12.00	12.00			16.00		16.00	84.0	
335+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
338+00	NB	DL	10.00	12.00		13.33			13.33	78.0	
339+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
340+00	NB	DL	10.00	12.00		13.33			13.33	78.0	
357+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
358+00	NB	DL	15.00	6.00		10.00			10.00	69.0	
358+25	NB	DL	15.00	12.00			20.00		20.00	93.0	
358+50	NB	DL	8.00	12.00		10.67			10.67	72.0	
359+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
359+25	NB	DL	6.00	6.00	4.00				4.00	42.0	
360+00	NB	DL	15.00	12.00			20.00		20.00	93.0	
363+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
370+20	NB	DL	6.00	6.00	4.00				4.00	42.0	
371+00	NB	DL	6.00	12.00		8.00			8.00	66.0	
373+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
373+25	NB	DL	10.00	6.00		6.67			6.67	54.0	
375+00	NB	DL	8.00	6.00		5.33			5.33	48.0	
375+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
378+00	NB	DL	6.00	12.00		8.00			8.00	66.0	
381+00	NB	DL	6.00	12.00		8.00			8.00	66.0	
391+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
395+20	NB	DL	6.00	6.00	4.00				4.00	42.0	
399+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
400+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
400+20	NB	DL	6.00	6.00	4.00				4.00	42.0	
402+50	NB	DL	6.00	6.00	4.00				4.00	42.0	
408+50	NB	DL	10.00	6.00		6.67			6.67	54.0	
442+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
449+00	NB	DL	8.00	12.00		10.67			10.67	72.0	
SUB-TOTAL =					68.0	100.7	72.7	0.0	241.3	1806.0	28

*LONGITUDINAL BARS ARE #7

FILE NAME =	USER NAME = kedaser	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\dot\kedaser\d0329897\0570980-sht-plans.dgn		DRAWN -	REVISED -		39	D5 PATCHING 2013-4	McLEAN	19	13			
MODELNAME	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -		SCALE: SHEET 3 OF 7 SHEETS STA. TO STA.			CONTRACT NO. 70980				
	PLOT DATE = 1/24/2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							