

SCHEDULE OF QUANTITIES

CLASS A PATCHING, 10" (CONT'D)

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200549	44200553	44200557	44200559	44213000	44213200	44213204
					TYPE I 10.0" (sq. yd)	TYPE II 10.0" (sq. yd)	TYPE III 10.0" (sq. yd)	TYPE IV 10.0" (sq. yd)	PATCHING REINFORCEMENT (sq. yd)	SAW CUTS (ft)	TIE BARS 3/4" (each)
451+00	NB	DL	8.00	12.00		10.67			10.67	72.0	
451+20	NB	DL	8.00	12.00		10.67			10.67	72.0	
452+00	NB	DL	8.00	12.00		10.67			10.67	72.0	
462+00	NB	DL	6.00	6.00	4.00				4.00	42.0	
474+00	NB	DL	6.00	12.00		8.00			8.00	66.0	
476+20	NB	DL	6.00	6.00	4.00				4.00	42.0	
509+50	NB	DL	6.00	12.00		8.00			8.00	66.0	
510+50	NB	DL	6.00	12.00		8.00			8.00	66.0	
513+00	NB	DL	6.00	12.00		8.00			8.00	66.0	
238+00	SB	DL	10.00	6.00		6.67			6.67	54.0	
238+50	SB	DL	20.00	6.00		13.33			13.33	84.0	22
239+00	SB	DL	25.00	6.00			16.67		16.67	99.0	28
240+00	SB	DL	6.00	12.00		8.00			8.00	66.0	
243+50	SB	DL	6.00	12.00		8.00			8.00	66.0	
243+75	SB	DL	6.00	6.00	4.00				4.00	42.0	
244+00	SB	DL	6.00	6.00	4.00				4.00	42.0	
252+00	SB	DL	6.00	6.00	4.00				4.00	42.0	
252+50	SB	DL	20.00	6.00		13.33			13.33	84.0	22
253+50	SB	DL	6.00	12.00		8.00			8.00	66.0	
254+00	SB	DL	6.00	6.00	4.00				4.00	42.0	
254+50	SB	DL	6.00	6.00	4.00				4.00	42.0	
255+00	SB	DL	15.00	6.00		10.00			10.00	69.0	
255+50	SB	DL	6.00	6.00	4.00				4.00	42.0	
255+75	SB	DL	12.00	6.00		8.00			8.00	60.0	
256+00	SB	DL	6.00	6.00	4.00				4.00	42.0	
258+00	SB	DL	10.00	6.00		6.67			6.67	54.0	
274+50	SB	DL	6.00	6.00	4.00				4.00	42.0	
278+50	SB	DL	6.00	6.00	4.00				4.00	42.0	
279+75	SB	DL	6.00	6.00	4.00				4.00	42.0	
280+00	SB	DL	6.00	12.00		8.00			8.00	66.0	
SUB-TOTAL =					48.0	154.0	16.7	0.0	218.7	1752.0	72

*LONGITUDINAL BARS ARE #7