

SCHEDULE OF QUANTITIES

CLASS A PATCHING, 10" (CONT'D)

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200549	44200553	44200557	44200559	44213000	44213200	44213204
					TYPE I 10.0" (sq. yd)	TYPE II 10.0" (sq. yd)	TYPE III 10.0" (sq. yd)	TYPE IV 10.0" (sq. yd)	PATCHING REINFORCEMENT (sq. yd)	SAW CUTS (ft)	TIE BARS 3/4" (each)
283+00	SB	DL	20.00	6.00		13.33			13.33	84.0	22
284+00	SB	DL	6.00	6.00	4.00				4.00	42.0	
284+50	SB	DL	10.00	6.00		6.67			6.67	54.0	
286+75	SB	DL	50.00	6.00				33.33	33.33	174.0	52
287+50	SB	DL	6.00	6.00	4.00				4.00	42.0	
295+00	SB	DL	10.00	6.00		6.67			6.67	54.0	
295+50	SB	DL	10.00	12.00		13.33			13.33	78.0	
297+50	SB	DL	6.00	6.00	4.00				4.00	42.0	
298+00	SB	DL	6.00	6.00	4.00				4.00	42.0	
298+50	SB	DL	20.00	6.00		13.33			13.33	84.0	22
299+00	SB	DL	6.00	12.00		8.00			8.00	66.0	
290+75	SB	DL	6.00	12.00		8.00			8.00	66.0	
300+25	SB	DL	20.00	12.00				26.67	26.67	108.0	22
307+50	SB	DL	6.00	12.00		8.00			8.00	66.0	
308+50	SB	DL	6.00	12.00		8.00			8.00	66.0	
309+80	SB	DL	8.00	12.00		10.67			10.67	72.0	
313+50	SB	DL	6.00	12.00		8.00			8.00	66.0	
313+75	SB	DL	6.00	12.00		8.00			8.00	66.0	
314+00	SB	DL	6.00	12.00		8.00			8.00	66.0	
315+00	SB	DL	6.00	12.00		8.00			8.00	66.0	
316+00	SB	DL	6.00	6.00	4.00				4.00	42.0	
315+50	SB	DL	8.00	6.00		5.33			5.33	48.0	
328+50	SB	DL	12.00	12.00			16.00		16.00	84.0	
330+25	SB	DL	6.00	6.00	4.00				4.00	42.0	
331+50	SB	DL	6.00	12.00		8.00			8.00	66.0	
332+60	SB	DL	8.00	12.00		10.67			10.67	72.0	
334+00	SB	DL	10.00	12.00		13.33			13.33	78.0	
338+50	SB	DL	6.00	6.00	4.00				4.00	42.0	
338+75	SB	DL	6.00	6.00	4.00				4.00	42.0	
339+00	SB	DL	6.00	6.00	4.00				4.00	42.0	
347+50	SB	DL	6.00	12.00		8.00			8.00	66.0	
352+75	SB	DL	15.00	6.00		10.00			10.00	69.0	
SUB-TOTAL =					36.0	183.3	16.0	60.0	295.3	2097.0	118

*LONGITUDINAL BARS ARE #7