

## SCHEDULE OF QUANTITIES

### CLASS A PATCHING, 10" (CONT'D)

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200549 TYPE I 10.0" (sq. yd)	44200553 TYPE II 10.0" (sq. yd)	44200557 TYPE III 10.0" (sq. yd)	44200559 TYPE IV 10.0" (sq. yd)	44213000 PATCHING REINFORCEMENT (sq. yd)	44213200 SAW CUTS (ft)	44213204 TIE BARS 3/4" (each)
353+00	SB	DL	15.00	6.00		10.00			10.00	69.0	
354+50	SB	DL	6.00	6.00	4.00				4.00	42.0	
366+00	SB	DL	15.00	6.00		10.00			10.00	69.0	
376+60	SB	DL	10.00	12.00		13.33			13.33	78.0	
376+80	SB	DL	10.00	12.00		13.33			13.33	78.0	
377+00	SB	DL	6.00	12.00		8.00			8.00	66.0	
380+00	SB	DL	6.00	12.00		8.00			8.00	66.0	
385+50	SB	DL	20.00	12.00			26.67	26.67	26.67	108.0	
400+50	SB	DL	8.00	6.00		5.33			5.33	48.0	
470+00	SB	DL	6.00	12.00		8.00			8.00	66.0	
471+88	SB	DL	15.00	6.00		10.00			10.00	69.0	

SUB-TOTAL =	4.0	86.0	0.0	26.7	116.7	759.0	0
NORTHBOUND TOTAL =	200.0	367.3	157.3	146.7	871.3	6,171.0	250
SOUTHBOUND TOTAL =	80.0	359.3	32.7	86.7	558.7	4,044.0	190
TOTAL =	280.0	726.7	190.0	233.3	1,430.0	10,215.0	440
USE =	280.0	727.0	190.0	234.0	1,430.0	10,215.0	440

\*LONGITUDINAL BARS ARE #7