

LOCATION OF WORK:

LOCATION #1

LOCATION #2
LOCATION #3B
LOCATION #4A

LOCATION #3A
LOCATION #4B

COUNTY:

F. A. P. 693
MCLEAN
RURAL

MCLEAN
URBAN

MCLEAN
RURAL

FUNDING BREAKOUT:

ROUT & SEAL
100% STATE

ROUT & SEAL
100% STATE

ROUT & SEAL
100% STATE

CONSTRUCTION TYPE CODE:

0005

0005

0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY
45100100	CRACK ROUTING (PAVEMENT)	FOOT	631910.0	25245.0	226745.0	379920.0
45100200	CRACK FILLING	POUND	252764.0	10098.0	90698.0	151968.0
67100100	MOBILIZATION	L SUM	1.0	0.1	0.4	0.5
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1.0		0.4	0.6
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	42.0		34.0	8.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0		0.4	0.6
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1.0			1.0
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	226190.0	3600.0	126950.0	95640.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	24.0		18.0	6.0

10

• SPECIALTY ITEMS

FILE NAME: c:\pwork\pwork\personb\0333662\09	USER NAME: personb	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0981-5ht-500.dgn		DRAWN: -	REVISED: -						VAR.		MCLEAN	26	9
PLOT SCALE: 40.0000 1/4 in.		CHECKED: -	REVISED: -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	DS CRACK & JOINT SEAL 2013-1 CONTRACT NO. 70981		
PLOT DATE: 2/1/2013		DATE: -	REVISED: -		ILLINOIS FED. AID PROJECT								