

SCHEDULE OF QUANTITIES

I-57 CLASS A 13" PATCHING										
STATION	LOCATION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA			SAW CUTS (FT)	TIE BARS 3/4" (EACH)	PATCHING REINFORCEMENT (SQ YD)
					TYPE I 13.0' ' 44200608 (SQ YD)	TYPE II 13.0' ' 44200610 (SQ YD)	TYPE IV 13.0' ' 44200614 (SQ YD)			
647+28.49	I-57 NB (URBAN)	DL	6	12	0.0	8.0	0.0	60.0	0	8.0
649+50.25	I-57 NB (URBAN)	DL	6	6	4.0	0.0	0.0	36.0	0	4.0
649+71.37	I-57 NB (URBAN)	DL	10	6	0.0	6.7	0.0	44.0	0	6.7
651+72.01	I-57 NB (URBAN)	DL	6	6	4.0	0.0	0.0	36.0	0	4.0
652+30.09	I-57 NB (URBAN)	DL	6	6	4.0	0.0	0.0	36.0	0	4.0
654+57.13	I-57 NB (URBAN)	DL	20	6	0.0	13.3	0.0	64.0	10	13.3
658+53.13	I-57 NB (URBAN)	DL	8	6	0.0	5.3	0.0	40.0	0	5.3
673+31.53	I-57 NB (URBAN)	DL	6	6	4.0	0.0	0.0	36.0	0	4.0
680+54.89	I-57 NB (URBAN)	DL	6	6	4.0	0.0	0.0	36.0	0	4.0
685+40.65	I-57 NB (RURAL)	DL	6	6	4.0	0.0	0.0	36.0	0	4.0
690+00.01	I-57 NB (RURAL)	DL	8	6	0.0	5.3	0.0	40.0	0	5.3
713+70.73	I-57 NB (RURAL)	DL	6	12	0.0	8.0	0.0	60.0	0	8.0
714+12.97	I-57 NB (RURAL)	DL	6	12	0.0	8.0	0.0	60.0	0	8.0
714+12.97	I-57 NB (RURAL)	PL	6	12	0.0	8.0	0.0	60.0	0	8.0
720+99.37	I-57 NB (RURAL)	DL	6	6	4.0	0.0	0.0	36.0	0	4.0
733+70.85	I-57 NB (RURAL)	DL	10	6	0.0	6.7	0.0	44.0	0	6.7
733+98.25	I-57 NB (RURAL)	DL	10	6	0.0	6.7	0.0	44.0	0	6.7
743+59.21	I-57 NB (RURAL)	DL	40	6	0.0	0.0	26.7	104.0	20	26.7
764+39.53	I-57 NB (RURAL)	DL	20	6	0.0	13.3	0.0	64.0	10	13.3
777+24.96	I-57 NB (RURAL)	DL	50	6	0.0	0.0	33.3	124.0	25	33.3
789+97.44	I-57 NB (RURAL)	DL	40	6	0.0	0.0	26.7	104.0	20	26.7
I-57 CLASS A, 13" SUB TOTALS					28.0 (SQ YD)	89.3 (SQ YD)	86.7 (SQ YD)	1164.0 (FT)	85.0 (EACH)	204.0 (SQ YD)