

SCHEDULE OF QUANTITIES

I-57 CLASS A 13" PATCHING CONT.										
STATION	LOCATION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA			SAW CUTS (FT)	TIE BARS 3/4" (EACH)	PATCHING REINFORCEMENT (SQ YD)
					TYPE I 13.0' ' 44200608 (SQ YD)	TYPE II 13.0' ' 44200610 (SQ YD)	TYPE IV 13.0' ' 44200614 (SQ YD)			
792+61.44	I-57 NB (RURAL)	DL	40	6	0.0	0.0	26.7	104.0	20	26.7
793+77.60	I-57 NB (RURAL)	DL	40	6	0.0	0.0	26.7	104.0	20	26.7
796+68.00	I-57 NB (RURAL)	DL	80	6	0.0	0.0	53.3	184.0	40	53.3
800+90.40	I-57 NB (RURAL)	DL	6	6	4.0	0.0	0.0	36.0	0	4.0
806+39.52	I-57 NB (RURAL)	DL	6	6	4.0	0.0	0.0	36.0	0	4.0
811+93.92	I-57 NB (RURAL)	DL	10	6	0.0	6.7	0.0	44.0	0	6.7
814+42.08	I-57 NB (RURAL)	DL	15	6	0.0	10.0	0.0	54.0	0	10.0
817+80.00	I-57 NB (RURAL)	DL	40	6	0.0	0.0	26.7	104.0	20	26.7
819+59.52	I-57 NB (RURAL)	DL	12	6	0.0	8.0	0.0	48.0	0	8.0
I-57 CLASS A, 13" SUB TOTALS					8.0 (SQ YD)	24.7 (SQ YD)	133.3 (SQ YD)	714.0 (FT)	100.0 (EACH)	166.0 (SQ YD)

	PATCH AREA			SAW CUTS (FT)	TIE BARS 3/4" (EACH)	PATCHING REINFORCEMENT (SQ YD)
	TYPE I 13.0' ' 44200608 (SQ YD)	TYPE II 13.0' ' 44200610 (SQ YD)	TYPE IV 13.0' ' 44200614 (SQ YD)			
I-57 CLASS A, 13" PATCHING TOTALS	36.0 (SQ YD)	114.0 (SQ YD)	220.0 (SQ YD)	1878.0 (FT)	185.0 (EACH)	370.0 (SQ YD)

*CHAMPAIGN & VERMILION