

**HMA REMOVAL TREATMENT FOR SHOULDERS, LEFT SIDE**

LOCATION	SHOULDER WIDTH	DISTANCE OF RUN	SHOULDER AREA	HMA SURFACE REMOVAL, VARIABLE DEPTH (3/4" AVG. @ E.O.P.)	HMA SURFACE REMOVAL, 2 1/4"
	(FOOT)	(FOOT)	(SQ FT)	(SQ YD)	(SQ YD)
<b>US 136, MAINLINE</b>					
STA 164+17.80 TO STA 169+50.00	VARIES	532.20	CADD	-	458.70
STA 169+50.00 TO STA 180+00.00	8.8 AVG.	1050.00	9240.00	1026.67	-
STA 180+00.00 TO STA 197+00.00	9.3 AVG.	1700.00	15810.00	1756.67	-
STA 197+00.00 TO STA 212+58.00	8.9 AVG.	1558.00	13866.20	1540.69	-
STA 212+58.00 TO STA 213+34.00	10.0 AVG.	76.00	760.00	84.44	-
STA 213+34.00 TO STA 214+00.00	10.0 AVG.	66.00	660.00	73.33	-
STA 214+00.00 TO STA 231+00.00	10.0 AVG.	1700.00	17000.00	1888.89	-
STA 231+00.00 TO STA 239+14.00	10.0 AVG.	814.00	8140.00	904.44	-
STA 239+14.00 TO STA 240+08.00	10.0 AVG.	94.00	940.00	-	-
STA 240+08.00 TO STA 246+40.00	10.0 AVG.	632.00	6508.00	723.11	-
STA 246+40.00 TO STA 247+37.00	VARIES	97.00	CADD	-	79.71
<b>TOTALS =</b>				<b>7998.24</b>	<b>538.41</b>

**HMA REMOVAL TREATMENT FOR SHOULDERS, RIGHT SIDE**

LOCATION	SHOULDER WIDTH	DISTANCE OF RUN	SHOULDER AREA	HMA SURFACE REMOVAL, VARIABLE DEPTH (3/4" AVG. @ E.O.P.)	HMA SURFACE REMOVAL, 2 1/4"
	(FOOT)	(FOOT)	(SQ FT)	(SQ YD)	(SQ YD)
<b>US 136, MAINLINE</b>					
STA 166+10.41 TO STA 169+50.00	VARIES	339.59	CADD	-	319.12
STA 169+50.00 TO STA 180+00.00	9.3 AVG.	1050.00	9765.00	1085.00	-
STA 180+00.00 TO STA 197+00.00	9.8 AVG.	1700.00	16660.00	1851.11	-
STA 197+00.00 TO STA 212+58.00	10.6 AVG.	1558.00	16514.80	1834.98	-
STA 212+58.00 TO STA 213+34.00	9.5 AVG.	76.00	722.00	-	-
STA 213+34.00 TO STA 214+00.00	9.5 AVG.	66.00	627.00	69.67	-
STA 214+00.00 TO STA 231+00.00	9.5 AVG.	1700.00	16150.00	1794.44	-
STA 231+00.00 TO STA 239+14.00	9.5 AVG.	814.00	7733.00	859.22	-
STA 239+14.00 TO STA 240+08.00	9.5 AVG.	94.00	893.00	99.22	-
STA 240+08.00 TO STA 246+40.00	9.5 AVG.	632.00	6377.84	708.65	-
STA 246+40.00 TO STA 247+37.00	VARIES	97.00	CADD	-	94.87
<b>TOTALS =</b>				<b>8302.29</b>	<b>413.99</b>

**HOT-MIX ASPHALT SURFACE REMOVAL, MAINLINE PAVEMENT**

LOCATION	PAVEMENT WIDTH	DISTANCE OF RUN	PAVEMENT AREA	HMA SURFACE REMOVAL, VAR. DEPTH (3/4" @ C.L.)	HMA SURFACE REMOVAL, 2 1/4"
				(SQ YD)	(SQ YD)
<b>US 136, MAINLINE</b>					
BEGINNING OF PROJECT US 136					
STA 426+10.00 TO STA 430+69.17	VARIES	459.17	1553.89		1553.89
STA. EQ.: STA. 430+69.17(BK) = STA. 0+00 (AHD)					
STA 0+00.00 TO STA 10+00.00	VARIES	1000.00	5474.11		5474.11
STA 10+00.00 TO STA 14+50.00	VARIES	450.00	1581.11		1581.11
STA 14+50.00 TO STA 27+00.00	VARIES	1250.00	3486.29	3486.29	
STA 27+00.00 TO STA 44+00.00	25	1700.00	4733.22	4733.22	
STA 44+00.00 TO STA 61+00.00	25	1700.00	4731.67	4731.67	
STA 61+00.00 TO STA 78+00.00	25	1700.00	4738.67	4738.67	
STA 78+00.00 TO STA 95+00.00	25	1700.00	4741.11	4741.11	
STA 95+00.00 TO STA 112+00.00	25	1700.00	4740.67	4740.67	
STA 112+00.00 TO STA 129+00.00	25	1700.00	4739.00	4739.00	
STA 129+00.00 TO STA 134+12.27	25	512.27	1427.89	1427.89	
RAILROAD OMISSION					
STA 134+82.38 TO STA 146+00.00	25	1117.62	3116.89	3116.89	
STA 146+00.00 TO STA 149+00.00	VARIES	300.00	836.67	836.67	
STA 149+00.00 TO STA 163+00.00	VARIES	1400.00	6707.11		6707.11
STA 163+00.00 TO STA 169+50.00	VARIES	650.00	2298.11		2298.11
STA 169+50.00 TO STA 180+00.00	VARIES	1050.00	3003.11	3003.11	
STA 180+00.00 TO STA 197+00.00	VARIES	1700.00	4620.78	4620.78	
STA 197+00.00 TO STA 214+00.00	24	1700.00	4533.33	4533.33	
STA 214+00.00 TO STA 231+00.00	24	1700.00	4533.33	4533.33	
STA 231+00.00 TO STA 246+40.00	24	1540.00	4106.67	4106.67	
STA 246+40.00 TO STA 248+00.00	VARIES	160.00	441.22		441.22
STA 248+00.00 TO STA 254+45.00	26	645.00	1870.33		1870.33
STA 254+45.00 TO STA 255+27.47	VARIES	82.47	301.78		301.78
STA 255+27.47 TO STA 261+63.59	34	636.12	2403.12		2403.12
STA. EQ.: STA. 261+63.59(BK) = STA. 0+00 (AHD)					
STA 0+00.00 TO STA 4+90.00	34	490.00	1851.11		1851.11
END OF PROJECT US 136					
IL RTE. 29 SOUTH LEG	27 & VARIES	278.71	1539.00		1539.00
IL RTE. 29 NORTH LEG	28 & VARIES	220.81	1270.44		1270.44
<b>TOTALS =</b>			<b>85380.63</b>	<b>58089.30</b>	<b>27291.33</b>