

PAINT PAVEMENT MARKING - LINE 5"				
LOCATION			COLOR / DESCRIPTION	LENGTH (FOOT)
US 136 MAINLINE				
LEFT SIDE E.O.P.				
STA 14+00.00	TO	STA 55+06.00	WHITE, SOLID	4106
STA 55+78.00	TO	STA 107+65.00	WHITE, SOLID	5187
STA 108+59.00	TO	STA 134+42.00	WHITE, SOLID	2583
STA 134+52.00	TO	STA 149+00.00	WHITE, SOLID	1448
STA 169+50.00	TO	STA 239+04.00	WHITE, SOLID	6954
STA 240+17.00	TO	STA 247+90.00	WHITE, SOLID	773
RIGHT SIDE E.O.P.				
STA 14+00.00	TO	STA 55+47.00	WHITE, SOLID	4147
STA 56+33.00	TO	STA 120+70.00	WHITE, SOLID	6437
STA 121+53.00	TO	STA 132+10.00	WHITE, SOLID	1057
STA 133+01.00	TO	STA 134+42.00	WHITE, SOLID	141
STA 134+52.00	TO	STA 149+00.00	WHITE, SOLID	1448
STA 169+50.00	TO	STA 212+50.00	WHITE, SOLID	4300
STA 213+44.00	TO	STA 247+45.00	WHITE, SOLID	3401
CENTER LINE (10' DASH - 30' SKIP)				
STA 14+00.00	TO	STA 134+42.00	YELLOW	12042
STA 134+52.00	TO	STA 149+00.00	YELLOW	1448
STA 169+50.00	TO	STA 246+40.00	YELLOW	7690
* NO PASSING LINE, EASTBOUND TRAFFIC				
STA 124+79.00	TO	STA 134+42.00	YELLOW, SOLID	963
STA 147+61.00	TO	STA 149+00.00	YELLOW, SOLID	139
* NO PASSING LINE, WESTBOUND TRAFFIC				
STA 14+00.00	TO	STA 16+32.00	YELLOW, SOLID	232
STA 134+52.00	TO	STA 144+16.00	YELLOW, SOLID	964
TOTAL =				65460

* - PLACEMENT OF NO PASSING LINES SHALL BE VERIFIED BY THE ENGINEER.

SHORT-TERM PAVEMENT MARKING, 4"					
LOCATION			CENTERLINE APPLICATION, 4' PER 40' (3 APPLICATIONS)	SHOULDER APPLICATION, 4' PER 100' (BOTH SIDES, 2 APPLICATIONS)	WORK ZONE PAVEMENT MARKING REMOVAL (1 APPLICATION)
			(FOOT)	(FOOT)	(SQ FT)
US 136, MAINLINE					
STA 426+00.00	TO	STA 430+69.17	141	75	84
STA. EQUATION: STA. 430+69.17(BK) = STA. 0+00 (AHD)					
STA 0+00.00	TO	STA 134+42.00	4033	2151	2420
RAILROAD OMISSION					
STA 134+52.00	TO	STA 247+37.00	3386	1806	2031
STA 247+37.00	TO	STA 261+63.59	428	-	143
STA. EQUATION: STA. 261+63.59(BK) = STA. 0+00 (AHD)					
STA 0+00.00	TO	STA 5+00.00	150	-	50
TOTAL =			12168		4728