

OUTSIDE MPO SIGNING SCHEDULE (CONTINUED)

PROPOSED LOCATION	MUTCD	DESCRIPTION	DIMENSIONS	AREA OF EACH SIGN (SQ FT)	NO. OF SIGNS	PR POST LENGTH EACH SIGN (FOOT)	SIGN PANELS			REMOVE SIGN PANEL ASSY		REMOVAL SIGN PANELS		RELOCATE SIGN PANELS		POSTS		FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION
							TYPE 1	TYPE 2	TYPE 3	TYPE A	TYPE B	TYPE 1	TYPE 2	TYPE 1	TYPE 2	WOOD POST	STEEL POST	
							72000100 (SQ FT)	72000200 (SQ FT)	72000300 (SQ FT)	72400100 (EACH)	72400200 (EACH)	72400310 (SQ FT)	72400320 (SQ FT)	72400710 (SQ FT)	72400720 (SQ FT)	73000100 (FOOT)	72800100 (FOOT)	
16	I-72 EXIT 93, VETERANS PARKWAY INTERCHANGE (SEE SHEET 34)																	
	W13-7	RAMP CURVE 25 MPH	36"X60"	15.0	1			15										
	W1-13R	TRUCK OVERTURN	30"X30"	6.25	1		6.25											
	W13-1P	25 MPH	18"X18"	2.25	1		2.25											
	W13-6	EXIT CURVE 25 MPH	36"X60"	15.0	1			15										
	REMOVAL	RAMP 25 MPH	36"X42"	10.5	1							10.5						
24	EB I-72 EXIT 60, US 67 INTERCHANGE (SEE SHEET 35)																	
	W1-8	CHEVRON	18"X24"	3.0	24	14	72											336
	W13-7	RAMP CURVE 25 MPH	36"X60"	15.0	2	8		30								16		
	W13-6	EXIT CURVE 25 MPH	36"X60"	15.0	1		15											
	REMOVAL	RAMP 30 MPH	36"X42"	10.5	2							21.00						
25	WB I-72 EXIT 60, US 67 INTERCHANGE (SEE SHEET 36)																	
	W1-8	CHEVRON	18"X24"	3.0	24	14	72											336
	W13-7	RAMP CURVE 25 MPH	36"X60"	15.0	2	8		30								16		
	W13-6	EXIT CURVE 25 MPH	36"X60"	15.0	1		15											
	REMOVAL	RAMP 30 MPH	36"X42"	10.5	2							21.00						
20	I-72 /US 36 & FAI 172 (SEE SHEET 37)																	
	W1-8	CHEVRON	18"X24"	3.0	3	14	9											42
	W13-7	RAMP CURVE 25 MPH	36"X60"	15.0	1	18		15								18		1
	REMOVAL	RAMP 35 MPH	36"X42"	10.5	1							10.50						
	RELOCATE	RAMP 35 MPH	36"X42"	10.5	1	16								10.5		16		
	RELOCATE	TRUCK OVERTURN	30"X30"	6.25	1								6.25					
	REMOVAL	TRUCK OVERTURN	30"X30"	6.25	1				1									
	REMOVAL	35 MPH	18"X18"	2.25	1													
	RELOCATE	35 MPH	18"X18"	2.25	1	16							2.25			16		
26	US 67 & IL 104/ IL78 INTERCHANGE (SEE SHEET 38)																	
	W1-8	CHEVRON	18"X24"	3.0	2	14	6											28
	W13-7	RAMP CURVE 25 MPH	36"X60"	15.0	2	16		30								32		
	REMOVAL	TRUCK OVERTURN	30"X30"	6.25	1													
	REMOVAL	25 MPH	18"X18"	2.25	1				1									

SUBTOTALS (OUTSIDE MPO)	431	375	0	1	1	13	173	9	21	242	1862	1
-------------------------	-----	-----	---	---	---	----	-----	---	----	-----	------	---

	SIGN PANELS			REMOVE SIGN PANEL ASSY		REMOVAL SIGN PANELS		RELOCATE SIGN PANELS		POSTS		FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION
	TYPE 1	TYPE 2	TYPE 3	TYPE A	TYPE B	TYPE 1	TYPE 2	TYPE 1	TYPE 2	WOOD POST	STEEL POST	
	72000100 (SQ FT)	72000200 (SQ FT)	72000300 (SQ FT)	72400100 (EACH)	72400200 (EACH)	72400310 (SQ FT)	72400320 (SQ FT)	72400710 (SQ FT)	72400720 (SQ FT)	73000100 (FOOT)	72800100 (FOOT)	
SUBTOTALS (INSIDE MPO)	363	255	182	0	1	9	95	8	0	100	1540	0
SUBTOTALS (OUTSIDE MPO)	431	375	0	1	1	13	173	9	21	242	1862	1

TOTALS	794	630	182	1	2	22	268	17	21	342	3402	1
--------	-----	-----	-----	---	---	----	-----	----	----	-----	------	---