


INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1.	COVER SHEET
2.	INDEX OF SHEETS, STANDARDS, GENERAL NOTES & SIGNATURE
3-4.	SUMMARY OF QUANTITIES
5.	SCHEDULE OF QUANTITIES
6.	PROJECT LOCATION MAP
7.	PROJECT TYPICAL SECTIONS

STANDARDS

STANDARD NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
442001-04	CLASS A PATCHES
701101-03	OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701106-02	OFF-RD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701400-06	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-07	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-08	LANE CLOSURE, MULTILANE AT ENTRANCE OR EXIT RAMP, FOR SPEEDS > 45 MPH
701446-04	TWO LANE CLOSURE, FREEWAY/EXPRESSWAY
701901-02	TRAFFIC CONTROL DEVICES
701406-07	



**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
DISTRICT 6**

EXAMINED 11 / 20 20 12
Bill Dwyer
ENGINEER OF OPERATIONS

EXAMINED OCT 25 20 12
Jim [Signature]
ENGINEER OF PROJECT IMPLEMENTATION

EXAMINED November 2 20 12
Laura R. Macovich
ENGINEER OF PROGRAM DEVELOPMENT

MIXTURE REQUIREMENTS		
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT		
LOCATION:	SHOULDER REPAIR	STRUCTURE REPAIR
MIXTURE USE(S):	LOWER LIFT	TOP LIFT
AC/PG:	PG 64-22	PG 64-22
DESIGN AIR VOIDS:	4.0% @ NS0	4.0% @ NS0
MIXTURE COMPOSITION:	IL 19.0	IL 9.5
FRICTION AGGREGATE:	N/A	MIX "C"

⚠ REVISSED 2-19-13