

PAVING

LOCATION	PAVEMENT WIDTH (FOOT)	LEFT SHOULDER WIDTH (FOOT)	RIGHT SHOULDER WIDTH (FOOT)	PAVEMENT AREA (SQYD)	SHOULDER AREA (SQYD)	BIT MATL PR CT (TON)	AGG PR CT (TON)	HMA LEVELING BINDER (TON)	HMA SURF COURSE, MIX "C" (TON)
IL 125									
STA 455+40.00 TO STA 472+69.16	24	4	4	4,611.09	1,221.92	2.22	23.33	193.67	387.33
STA 472+69.16 BK = STA 472+67.76 AH									
STA 472+67.76 TO STA 522+67.03	24	4	4	13,331.39	4,314.91	6.71	70.59	559.92	1,119.84
STA 522+67.03 BK = STA 522+71.69 AH									
STA 522+71.69 TO STA 549+81.64	24	4	4	7,226.53	2,408.84	3.66	38.54	303.51	607.03
STA 549+81.64 BK = STA 549+69.10 AH									
STA 549+69.10 TO STA 629+37.01	24	4	4	21,247.76	6,955.12	10.72	112.81	892.41	1,784.81
STA 629+37.01 BK = STA 629+30.80 AH									
STA 629+30.80 TO STA 729+13.82	24	4	4	26,621.39	8,620.20	13.39	140.97	1,118.10	2,236.20
STA 729+13.82 BK = STA 729+13.40 AH									
STA 729+13.40 TO STA 754+84.89	24	4	4	6,857.31	1,848.88	3.31	34.82	288.01	576.01
STA 754+84.89 BK = STA 754+84.34 AH									
STA 754+84.34 TO STA 767+85.66	24	4	4	3,470.19	1,156.73	1.76	18.51	145.75	291.50
STA 767+85.66 BK = STA 767+85.99 AH									
STA 767+85.99 TO STA 909+98.22	24	4	4	37,899.28	12,377.98	19.11	201.11	1,591.77	3,183.54
STA 909+98.22 BK = STA 909+97.41 AH									
STA 909+97.41 TO STA 918+19.03	24	4	4	2,188.83	729.61	1.11	11.67	91.93	183.86
STA 918+19.03 BK = STA 918+18.96 AH									
STA 918+18.96 TO STA 1015+00.00	24	4	4	25,816.11	8,460.48	13.03	137.11	1,084.28	2,168.55
STA 1015+00.00 TO STA 1033+91.74	24	10	10	5,044.64	3,919.42	3.41	35.86	211.87	423.75
STA 1033+91.74 BK = STA 1033+91.48 AH									
STA 1033+91.48 TO STA 1075+30.00	24	10	10	11,036.05	8,897.82	7.57	79.74	463.51	927.03
TOTAL						86.0	905.1	6,944.7	13,889.5

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\dot\sparksgw\10313888\0672F69-sht-schedule.dgn		DRAWN -	REVISED -						67	.	CASS	47	7
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: NTS				SHEET OF SHEETS STA. TO STA.				
	PLOT DATE = Oct-17-2012 12:27:26PM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT CONTRACT NO. 72F69								