

SHORT-TERM PAVEMENT MARKINGS

LOCATION	LINE 4'' YELLOW SKIP DASH (FOOT)	LINE 4'' WHITE EDGE LINE (FOOT)
IL 125		
STA 455+00.00 TO STA 472+69.16	531	
STA 472+69.16 BK = STA 472+67.76 AH		
STA 472+67.76 TO STA 522+67.03	1,500	
STA 522+67.03 BK = STA 522+71.69 AH		
STA 522+71.69 TO STA 542+34.00	589	
STA 542+34.00 TO STA 548+32.00	179	
STA 548+32.00 TO STA 549+24.00	28	
STA 549+24.00 TO STA 549+81.64	17	
STA 549+81.64 BK = STA 549+69.10 AH		
STA 549+69.10 TO STA 557+67.00	239	
STA 557+67.00 TO STA 629+37.01	2,151	
STA 629+37.01 BK = STA 629+30.80 AH		
STA 629+30.80 TO STA 729+13.82	2,995	
STA 729+13.82 BK = STA 729+13.40 AH		
STA 729+13.40 TO STA 754+84.89	771	
STA 754+84.89 BK = STA 754+84.34 AH		
STA 754+84.34 TO STA 763+10.00	248	
STA 763+10.00 TO STA 767+85.66	143	
STA 767+85.66 BK = STA 767+85.99		
STA 767+85.99 TO STA 767+90.00	1	
STA 767+90.00 TO STA 769+60.00	51	
STA 769+60.00 TO STA 779+80.00	306	
STA 779+80.00 TO STA 909+98.22	3,905	
STA 909+98.22 BK = STA 909+97.41 AH		
STA 909+98.22 TO STA 918+19.03	246	
STA 918+19.03 BK = STA 918+18.96 AH		
STA 918+18.96 TO STA 1015+00.00	2,904	
STA 1015+00.00 TO STA 1026+84.03	355	284
STA 1026+84.03 TO STA 1033+91.74	168	135
STA 1033+91.74 BK = STA 1033+91.48 AH		
STA 1033+91.48 TO STA 1075+30.00	1,242	993
TOTAL	18,570	1,412

GRAND TOTAL - SHORT TERM 19,982

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	LINE 4'' YELLOW SKIP DASH (SQ FT)	LINE 4'' WHITE EDGE LINE (SQ FT)
IL 125		
STA 455+00.00 TO STA 472+69.16	59	
STA 472+69.16 BK = STA 472+67.76 AH		
STA 472+67.76 TO STA 522+67.03	167	
STA 522+67.03 BK = STA 522+71.69 AH		
STA 522+71.69 TO STA 542+34.00	65	
STA 542+34.00 TO STA 548+32.00	20	
STA 548+32.00 TO STA 549+24.00	3	
STA 549+24.00 TO STA 549+81.64	2	
STA 549+81.64 BK = STA 549+69.10 AH		
STA 549+69.10 TO STA 557+67.00	27	
STA 557+67.00 TO STA 629+37.01	239	
STA 629+37.01 BK = STA 629+30.80 AH		
STA 629+30.80 TO STA 729+13.82	333	
STA 729+13.82 BK = STA 729+13.40 AH		
STA 729+13.40 TO STA 754+84.89	86	
STA 754+84.89 BK = STA 754+84.34 AH		
STA 754+84.34 TO STA 763+10.00	28	
STA 763+10.00 TO STA 767+85.66	16	
STA 767+85.66 BK = STA 767+85.99		
STA 767+85.99 TO STA 767+90.00		
STA 767+90.00 TO STA 769+60.00	6	
STA 769+60.00 TO STA 779+80.00	34	
STA 779+80.00 TO STA 909+98.22	434	
STA 909+98.22 BK = STA 909+97.41 AH		
STA 909+98.22 TO STA 918+19.03	27	
STA 918+19.03 BK = STA 918+18.96 AH		
STA 918+18.96 TO STA 1015+00.00	323	
STA 1015+00.00 TO STA 1026+84.03	39	32
STA 1026+84.03 TO STA 1033+91.74	19	15
STA 1033+91.74 BK = STA 1033+91.48 AH		
STA 1033+91.48 TO STA 1075+30.00	138	110
TOTAL	2,063	157

GRAND TOTAL - WZ PM REM 2,220

FILE NAME =	USER NAME = karnes	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pr-work\pavdot\karnes\0313088\0672F59-shr-schedule.dgn	DRAWN -	REVISED -	67						-	CASS	47	11	
Default	PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -		SCALE: NTS SHEET OF SHEETS STA. TO STA.				CONTRACT NO. 72F69				
	PLOT DATE = Mar-05-2013 09:22:19AM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								