

RESURFACING

LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MM), N70	HMA BINDER CSE, IL 19.0, N70	HMA SURF CSE, MIX "D", N70
	TON	TON	TON	TON	TON
6TH ST. RD.					
VARIABLE DEPTH LEVELING BINDER					
STA 100+80.00 TO STA 0+50.00			179.26		
STA 1+00.00 TO STA 2+30.44			5.89		
STA 11+50.00 TO STA 17+00.00			34.23		
LEVELING BINDER 3/4", SURFACE COURSE 1 1/2"					
6TH ST. RD.					
STA 100+42.22 TO STA 101+12.64	0.17	0.87	18.30		36.60
STA 101+12.64 TO STA 102+96.20	0.27	1.40	29.12		81.88
STA 102+96.20 TO STA 104+12.35	0.14	0.72	14.93		43.94
STA 0+00.00 TO STA 0+00.85	0.00	0.00	0.08		0.24
STA 0+00.85 TO STA 2+62.57	0.22	1.16	24.43		48.84
STA 2+62.57 TO STA 14+25.64	0.98	5.17	108.55		330.41
STA 14+25.64 TO STA 14+48.00	0.02	0.11	2.30		6.38
STA 14+48.00 TO STA 21+15.51	0.67	3.54	74.76		198.28
STA 21+15.51 TO STA 21+78.64	0.06	0.31	6.48		17.82
STA 21+78.64 TO STA 22+18.82	0.03	0.18	3.75		11.38
ST JOSEPH STREET					
STA 14+59.69 TO STA 15+00.41	0.07	0.36	7.64		17.91
FLORA AVE					
STA 9+60.04 TO STA 9+86.18	0.03	0.14	3.03		8.45
6TH ST FRONTAGE RD EAST					
STA 57+41.26 TO STA 59+29.96	0.29	1.55		108.59	65.15
STRAIGHT ST.					
STA 10+16.00 TO STA 11+01.94	0.12	0.65		45.34	27.20
TOTAL	3.07	16.16	512.75	153.93	894.48

PAVEMENT REMOVAL

LOCATION	SQ YD
6TH ST. RD	
STA 17+00.00 TO STA 18+44.59	253.92
6TH ST FRONTAGE RD EAST.	
STA 51+24.00 TO STA 59+29.96	1,835.23
STRAIGHT ST.	
STA 9+40.50 TO STA 9+88.72	245.50
TOTAL	2,334.65

COMBINATION CURB AND GUTTER REMOVAL

LOCATION	FOOT
6TH ST. RD	
LT STA 100+32.25 TO STA 100+67.85	82
RT STA 100+32.25 TO STA 100+67.79	70
RT STA 102+44.00 TO STA 102+64.38	30
RT STA 103+10.15 TO STA 103+45.80	65
TOTAL	247

SIDEWALK REMOVAL

LOCATION	SQ FT
BAKER DR.	
LT STA 10+64.00	26
RT STA 10+69.00	70
TOTAL	96

MEDIAN REMOVAL (SPECIAL)

LOCATION	SQ FT
BAKER DR.	
LT STA 10+35.55	49
LT STA 10+42.00	8
LT STA 10+45.00	8
RT STA 10+36.00	8
RT STA 10+42.00	8
RT STA 10+46.00	8
STRAIGHT ST	
LT STA 10+20.00	25
TOTAL	114

PAVED SHOULDER REMOVAL

LOCATION	SQ YD
6TH ST. RD	
RT STA 100+32.62 TO STA 101+12.64	89.61
RT STA 2+33.50 TO STA 4+32.75	77.62
TOTAL	167.23



JOB = 2265.11
 FILE NAME = D672F74-sht-Schedules.dgn
 PLOT SCALE = 20.0000' / IN.
 PLOT DATE = 2/4/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 10/8/2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.B.I. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
 126 (110) I-2 SANGAMON 93 20
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 72F74