

STP FUNDING IS WEST OF I-172 AND NHS FUNDING IS EAST OF I-172

LZAE		L050		CONSTRUCTION CODE			
STP FUNDS	NHS FUNDS						
80% FED	80% FED						
20% STATE	20% STATE						
ROADWAY	ROADWAY						
0005	0005						
RURAL	RURAL						

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LZAE	L050	CONSTRUCTION CODE			
60500060	REMOVING INLETS	EACH	2	1	1				
60608552	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	3453	1706	1747				
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	127	55	72				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	20390	9989	10401				
60624600	CORRUGATED MEDIAN	SO FT	1588	788	800				
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	550	275	275				
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	1	1				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	1	1				
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	7	4	3				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3				
67100100	MOBILIZATION	L SUM	1	0.5	0.5				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5				
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.5	0.5				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	5	5				

*SPECIALTY ITEM

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
q:\03\105\B0224\24\24 over frazer creek - roadway plans\us 24 g 1-172\cod		DRAWN De72F76-shi-Summary.dgn	REVISED						63	(HRS-6)	ADAMS	24	5	
PLOT SCALE = 1/8"=1'-0"		CHECKED	REVISED						SCALE: none SHEET NO. 3 OF 6 SHEETS STA. TO STA.				CONTRACT NO. 72F76	
PLOT DATE = 10/28/2012		DATE	REVISED						FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT					