

PREFORMED PLASTIC PAVEMENT MARKING
TYPE B - INLAID - LETTERS AND SYMBOLS

78004200

STATION TO STATION	SIDE	DESCRIPTION	WHITE	
			SO FT	
FAP 63 (US 24) - NHS FUNDING				
2166+06.8	2168+16.9	LT IS	TURN ARROWS	46.8
FAP 63 (US 24) - STP FUNDING				
2175+21.1	2177+32.8	RT IS	TURN ARROWS	46.8
RAMP A - NHS FUNDING				
19+61.1	20+51.3	LT & RT	TURN ARROWS	31.2
RAMP C - STP FUNDING				
22+12.6	23+41.2	LT & RT	TURN/WRONG WAY ARROWS	24.3
TOTAL			149.1	
USE			150	

PREFORMED PLASTIC PAVEMENT MARKING
TYPE B - INLAID - LINE 24"

78004280

STATION TO STATION	SIDE	DESCRIPTION	WHITE	
			FOOT	
RAMP A - NHS FUNDING				
19+61.1	20+51.3	LT & RT	STOP BAR	36.0
RAMP C - STP FUNDING				
22+12.6	23+41.2	LT & RT	STOP BAR	36.0
TOTAL			72.0	
USE			72	

MODIFIED URETHANE PAVEMENT MARKING - LINE 6"

78009006

STATION TO STATION	SIDE	DESCRIPTION	WHITE	
			FOOT	
FAP 63 (US 24) - NHS FUNDING				
2166+06.8	2168+16.9	LT IS	TURN LANE	210.1
2168+16.9	2170+86.9	LT IS	SKIP-DASH	68.0
FAP 63 (US 24) - STP FUNDING				
2172+51.1	2175+21.1	RT IS	SKIP-DASH	68.0
2175+21.1	2177+32.8	RT IS	TURN LANE	211.8
RAMP A - NHS FUNDING				
19+61.1	20+51.3	LT	LANE LINE	31.8
TOTAL			589.7	
USE			590	

MODIFIED URETHANE PAVEMENT MARKING - LINE 8"

78009008

STATION TO STATION	SIDE	DESCRIPTION	WHITE	
			FOOT	
RAMP A - NHS FUNDING				
19+61.1	20+51.3	LT & RT	CHANNELIZATION	204.3
RAMP C - STP FUNDING				
22+12.6	23+41.2	LT & RT	CHANNELIZATION	175.5
TOTAL			379.8	
USE			380	

MODIFIED URETHANE PAVEMENT MARKING - LINE 12"

78009012

STATION TO STATION	SIDE	DESCRIPTION	WHITE	YELLOW
			FOOT	FOOT
FAP 63 (US 24) - NHS FUNDING				
2157+00.0	2158+48.7	CL	CHANNELIZATION	27.9
FAP 63 (US 24) - STP FUNDING				
2184+59.8	2186+00.0	CL	CHANNELIZATION	24.3
RAMP A - NHS FUNDING				
19+61.1	20+51.3	LT & RT	CHANNELIZATION	96.8
RAMP C - STP FUNDING				
22+12.6	23+41.2	LT & RT	CHANNELIZATION	77.6
TOTALS			174.4	52.2
USE			227	

MODIFIED URETHANE PAVEMENT MARKING - LINE 5"

78009005

STATION TO STATION	SIDE	DESCRIPTION	WHITE	YELLOW	
			FOOT	FOOT	
FAP 63 (US 24) - NHS FUNDING					
2154+49.7	2157+00.0	CL	NO-PASSING	476.1	
2154+49.7	2171+69.0	LT OS	EDGE LINE	1553.5	
2154+49.7	2171+69.0	RT OS	EDGE LINE	1553.8	
2157+00.0	2165+11.3	LT IS	EDGE LINE	817.4	
2157+00.0	2165+11.3	RT IS	EDGE LINE	814.7	
2166+04.8	2171+69.0	LT IS	EDGE LINE	565.2	
2166+04.8	2171+69.0	RT IS	EDGE LINE	567.2	
FAP 63 (US 24) - STP FUNDING					
2171+69.0	2188+43.3	LT OS	EDGE LINE	1527.4	
2171+69.0	2188+43.3	RT OS	EDGE LINE	1506.2	
2171+69.0	2177+34.8	LT IS	EDGE LINE	568.8	
2171+69.0	2177+34.8	RT IS	EDGE LINE	570.9	
2178+18.9	2186+00.0	LT IS	EDGE LINE	785.4	
2178+18.9	2186+00.0	RT IS	EDGE LINE	786.9	
2186+00.0	2188+43.3	CL	NO-PASSING	493.2	
RAMP A - NHS FUNDING					
19+61.1	20+51.3	LT & RT	EDGE LINE	154.3	92.0
RAMP B - NHS FUNDING					
0+23.1	1+79.3	LT & RT	EDGE LINE	164.1	224.3
RAMP C - STP FUNDING					
22+12.6	23+41.2	LT & RT	EDGE LINE	214.9	132.7
RAMP D - STP FUNDING					
0+23.8	1+16.7	LT & RT	EDGE LINE	94.8	154.2
TOTALS			6769.0	7049.0	
USE			13818		

RAISED REFLECTIVE PAVEMENT MARKERS

78100100

STATION TO STATION	SIDE	MAXIMUM SPACING	EACH			
			1-WAY AMBER	1-WAY CRYSTAL	2-WAY AMBER	
FAP 63 (US 24) - NHS FUNDING						
2154+49.68	2156+20.00	CL	80		1	
2156+20.00	2157+00.00	LT CL	40		3	
2156+20.00	2157+00.00	RT CL	40		3	
2157+00.00	2158+48.71	LT CL	40		4	
2157+00.00	2158+48.71	RT CL	40		4	
2158+48.71	2165+11.30	LT	40	17		
2158+48.71	2165+11.30	RT	40	17		
2165+11.30	2165+11.30	RT	N/A	3		
2166+04.81	2166+04.81	LT	N/A	3		
2166+04.81	2168+16.92	LT	40	6	6	
2166+04.81	2168+16.92	RT	40	6		
FAP 63 (US 24) - STP FUNDING						
2175+21.08	2177+34.83	LT	40	6		
2175+21.08	2177+34.83	RT	40	6	6	
2177+34.83	2177+34.83	LT	N/A	3		
2178+18.86	2178+18.86	LT	N/A	3		
2178+18.86	2184+59.84	LT	40	17		
2178+18.86	2184+59.84	RT	40	17		
2184+59.84	2186+00.00	LT CL	40		4	
2184+59.84	2186+00.00	RT CL	40		4	
2186+00.00	2186+80.00	LT CL	40		3	
2186+00.00	2186+80.00	RT CL	40		3	
2186+80.00	2188+43.33	CL	80		1	
TOTALS				104	12	30
USE				146		

ESTIMATED STRIPING QUANTITIES

PAY ITEM NUMBER	PAY ITEM	UNIT	QUANTITY	LOCATION/REASON
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	AS REQUIRED FOR DROP-OFFS
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1104	TEMPORARY STRIPING ON BINDER/SURFACE
70300210	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SO FT	150	TEMPORARY STRIPING ON BINDER/SURFACE
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	13818	TEMPORARY STRIPING ON BINDER/SURFACE
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	590	TEMPORARY STRIPING ON BINDER/SURFACE
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	380	TEMPORARY STRIPING ON BINDER/SURFACE
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	227	TEMPORARY STRIPING ON BINDER/SURFACE
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	72	TEMPORARY STRIPING ON BINDER/SURFACE
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	6950	REMOVE SHORT-TERM/TEMPORARY STRIPING