

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY
				0005
				S.N.
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.6	7.6
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600990	TEMPORARY RAMP	SQ YD	28	28
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,587.00	1,587.00
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	19,975.00	19,975.00
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	200.0	200.0
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	250.0	250.0
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	500.0	500.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	124.0	124.0
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,410.0	1,410.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	235.0	235.0
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	23,761.0	23,761.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	89.0	89.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	89.0	89.0

NOTE:
 COST OF SAW CUTS AND BUTT JOINTS SHALL BE INCLUDED IN
 HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2" AND NOT PAID
 FOR SEPARATELY.

*SPECIALTY ITEM