

ILLINOIS DEPARTMENT OF TRANSPORTATION			80% FED 20% STATE TOTAL QUANTITIES	ACM M231		ACRS M232			
CODE NO	ITEM	UNIT		0005 MACON URBAN FAU 7464	0011 MACON URBAN FAU 7464	0005 MACON RURAL FAS 1536	0005 PIATT RURAL FAS 1536		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	85	85					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1					
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	174.8	174.8					
50800105	REINFORCEMENT BARS	POUND	700	700					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	65,760	65,760					
50800515	BAR SPLICERS	EACH	119	119					
51500100	NAME PLATES	EACH	1	1					
54003000	CONCRETE BOX CULVERTS	CU YD	168.9	168.9					
63000007	STEEL PLATE BEAM GUARDRAIL, TYPE B, 6 FOOT POSTS	FOOT	550	550					
63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	75	75					
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4					
63200310	GUARDRAIL REMOVAL	FOOT	464	464					
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	2	4				
67100100	MOBILIZATION	L SUM	1	1					

FILE NAME :	USER NAME : teasleyck	DESIGNED -	REVISED -
c:\pwork\pwidot\teasleyck\0121473\077	1156-shr-xoq.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / 1"	CHECKED -	REVISED -
	PLOT DATE = 10/30/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 3 OF 6 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**		Macon, Piatt	44	5
CONTRACT NO. 74156			ILLINOIS FED. AID PROJECT	

\*(125,126,126RIS-2&(126BR)B  
\*\*FAS 1536 & FAU 7464