

PARTIAL DEPTH PATCHING

Patch Number	Side	Station to Station	Length ft	Width ft	Plan Depth in	Area Sq Yd	Volume Cu Yd	Quantity Ton
1	NB	387+27 388+75	148	2	6.5	32.9	5.94	11.97
2	NB	389+83 390+13	30	2	6.5	6.7	1.20	2.43
3	NB	391+40 392+90	150	2	6.5	33.3	6.02	12.13
4	NB	394+30 396+40	210	2	6.5	46.7	8.43	16.99
5	NB	409+80 420+45	1065	2	6.5	236.7	42.73	86.15
6	NB	429+45 430+15	70	2	6.5	15.6	2.81	5.66
7	NB	441+70 450+74	904	2	6.5	200.9	36.27	73.12
8	NB	454+70 455+90	120	2	6.5	26.7	4.81	9.71
9	NB	459+90 461+45	155	2	6.5	34.4	6.22	12.54
10	NB	462+25 463+85	160	2	6.5	35.6	6.42	12.94
11	NB	473+90 475+25	135	2	6.5	30.0	5.42	10.92
12	NB	478+30 481+20	290	2	6.5	64.4	11.64	23.46
13	NB	484+42 489+30	488	2	6.5	108.4	19.58	39.47
14	NB	490+05 491+70	165	2	6.5	36.7	6.62	13.35
15	NB	493+10 495+20	210	2	6.5	46.7	8.43	16.99
16	NB	499+10 503+70	460	2	6.5	102.2	18.46	37.21
17	NB	529+90 531+20	130	2	6.5	28.9	5.22	10.52
18	NB	534+90 535+30	40	2	6.5	8.9	1.60	3.24
19	NB	542+64 545+30	266	2	6.5	59.1	10.67	21.52
20	NB	547+88 549+70	182	2	6.5	40.4	7.30	14.72
21	NB	555+86 556+85	99	2	6.5	22.0	3.97	8.01
22	NB	557+88 558+10	22	2	6.5	4.9	0.88	1.78
23	NB	559+80 560+55	75	2	6.5	16.7	3.01	6.07
24	NB	584+50 585+50	100	2	6.5	22.2	4.01	8.09
25	NB	594+60 595+60	100	2	6.5	22.2	4.01	8.09
26	NB	672+25 672+35	10	2	6.5	2.2	0.40	0.81
27	NB	686+45 687+30	85	2	6.5	18.9	3.41	6.88
28	NB	691+83 693+60	177	2	6.5	39.3	7.10	14.32
29	NB	744+35 747+00	265	2	6.5	58.9	10.63	21.44
30	NB	753+90 756+60	270	2	6.5	60.0	10.83	21.84
31	NB	781+00 781+95	95	2	6.5	21.1	3.81	7.68
32	NB	790+10 792+30	220	2	6.5	48.9	8.83	17.80
33	NB	793+20 796+45	325	2	6.5	72.2	13.04	26.29
34	NB	801+00 801+90	90	2	6.5	20.0	3.61	7.28
35	NB	805+90 809+30	340	2	6.5	75.6	13.64	27.50
36	NB	812+25 816+99	474	2	6.5	105.3	19.02	38.34
37	SB	774+90 776+30	140	2	6.5	31.1	5.62	11.32
38	SB	769+15 769+83	68	2	6.5	15.1	2.73	5.50
39	SB	764+80 766+30	150	2	6.5	33.3	6.02	12.13
40	SB	750+60 750+90	30	2	6.5	6.7	1.20	2.43
41	SB	741+15 742+00	85	2	6.5	18.9	3.41	6.88
42	SB	731+60 734+30	270	2	6.5	60.0	10.83	21.84
43	SB	722+30 723+45	115	2	6.5	25.6	4.61	9.30
44	SB	718+65 719+10	45	2	6.5	10.0	1.81	3.64
45	SB	715+20 716+70	150	2	6.5	33.3	6.02	12.13
46	SB	709+20 713+10	390	2	6.5	86.7	15.65	31.55
47	SB	702+00 702+45	45	2	6.5	10.0	1.81	3.64
48	SB	692+20 695+13	293	2	6.5	65.1	11.76	23.70
49	SB	662+15 663+10	95	2	6.5	21.1	3.81	7.68
50	SB	625+25 626+50	125	2	6.5	27.8	5.02	10.11

PARTIAL DEPTH PATCHING continued

Patch Number	Side	Station to Station	Length ft	Width ft	Plan Depth in	Area Sq Yd	Volume Cu Yd	Quantity Ton
51	SB	607+50 607+90	40	2	6.5	8.9	1.60	3.24
52	SB	579+60 583+98	438	2	6.5	97.3	17.57	35.43
53	SB	571+10 572+10	100	2	6.5	22.2	4.01	8.09
54	SB	567+50 568+50	100	2	6.5	22.2	4.01	8.09
55	SB	565+90 566+25	35	2	6.5	7.8	1.40	2.83
56	SB	562+40 564+75	235	2	6.5	52.2	9.43	19.01
57	SB	526+20 529+00	280	2	6.5	62.2	11.23	22.65
58	SB	510+60 511+85	125	2	6.5	27.8	5.02	10.11
59	SB	504+20 505+40	120	2	6.5	26.7	4.81	9.71
60	SB	495+30 496+40	110	2	6.5	24.4	4.41	8.90
61	SB	490+30 491+10	80	2	6.5	17.8	3.21	6.47
62	SB	479+80 480+30	50	2	6.5	11.1	2.01	4.04
63	SB	476+70 478+80	210	2	6.5	46.7	8.43	16.99
64	SB	471+60 472+10	50	2	6.5	11.1	2.01	4.04
65	SB	463+60 464+30	70	2	6.5	15.6	2.81	5.66
66	SB	458+30 459+40	110	2	6.5	24.4	4.41	8.90
67	SB	446+40 447+18	78	2	6.5	17.3	3.13	6.31
68	SB	444+30 445+40	110	2	6.5	24.4	4.41	8.90
69	SB	441+00 442+00	100	2	6.5	22.2	4.01	8.09
70	SB	439+40 440+38	98	2	6.5	21.8	3.93	7.93
71	SB	430+25 437+20	695	2	6.5	154.4	27.89	56.22
72	SB	433+80 434+80	100	2	6.5	22.2	4.01	8.09
73	SB	414+30 415+40	110	2	6.5	24.4	4.41	8.90
74	SB	404+50 408+00	350	2	6.5	77.8	14.04	28.31
75	SB	400+65 403+00	235	2	6.5	52.2	9.43	19.01
76	SB	397+50 398+00	50	2	6.5	11.1	2.01	4.04
77	SB	385+50 386+00	50	2	6.5	11.1	2.01	4.04
78	SB	312+90 313+90	100	2	6.5	22.2	4.01	8.09
TOTAL:						3190.0	575.97	1161.16

•(125,126,126R)RS-2&(126BR)B  
 \*\*FAS 1536 & FAU 7464

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PARTIAL DEPTH PATCHING SCHEDULE</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\dot\teasleyck\d0121473\0774156-sht-sch.dgn	DRAWN -	REVISED -	••			•	Macon, Platt	44	17	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 74156							
PLOT DATE = 10/30/2012	DATE -	REVISED -	SCALE:			SHEET 1	OF 1	SHEETS	STA.	TO STA.