

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	PAINT PAVEMENT MARKING - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKERS
258+22.0	285+56.0	2734	820	6152	91			6152	34
285+56.0	295+60.0	1004	301	2259	420			2259	13
295+60.0	610+34.0	31474	9442	71065	1049	190		71065	462
610+34.0	613+40.0	306	92	766	10			766	4
613+40.0	614+89.0	149	45	596	5			596	2
614+89.0	617+64.0	275	82	967	9			967	3
617+64.0	618+46.0	82	25	266	3			266	1
618+46.0	619+70.0	124	37	403	4			403	2
619+70.0	622+48.0	278	83	891	9			891	3
622+48.0	622+77.0	29	9	65	1			65	0
622+77.0	744+56.3	12179.3	3654	27891	406			27891	152
744+56.3	802+74.7	5818.4	1746	14399	194			14399	73
802+74.7	804+99.0	224.3	67	625	8	61	39	625	3
804+99.0	805+07.0	8	RAILROAD OMISSION						
805+07.0	816+92.0	1185	356	3832	40	61	39	3832	15
TOTALS:		16759	130177	2249	122	190	78	130177	767

PCC BASE COURSE WIDENING, 8"

STATION TO STATION	SIDE	LENGTH	WIDTH	QUANTITY	
287+65.00	292+47.00	LT	482	6	321.33
288+15.00	292+08.00	RT	393	2.3333	101.89
TOTAL:				423	

GUARDRAIL SCHEDULE

STATION TO STATION	SIDE	(FOOT)	(FOOT)	(EACH)	(EACH)	(FOOT)	
287+22.62	291+35.78	RT	275	37.5	2	2	234
288+76.89	292+89.38	LT	275	37.5	2	2	230
TOTALS:			550	75	4	4	464

EXCAVATING AND GRADING EXISTING SHOULDER

SIDE	STATION TO STATION	LENGTH	QUANTITY	
		(FOOT)	(UNIT)	
LT	258+22.0	286+86.0	2864	25
RT	258+22.0	292+08.0	3386	28
LT	293+46.0	610+34.0	31688	289
RT	292+08.0	610+34.0	31826	296
FRIENDS CREEK OMISSION				
RT	622+48.0	622+77.0	29	1
LT & RT	622+77.0	804+99.0	18222	352
RAILROAD OMISSION				
LT & RT	805+07.0	816+92.0	1185	24
TOTAL:				1015

•(125,126,126R)RS-2&(126BR)B
 ••FAS 1536 & FAU 7464

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -
ct:\pw\work\p\dot\teasleyck\d0121473\0774156-sht-sch.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -
	PLOT DATE = 10/30/2012	DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

MISCELLANEOUS SCHEDULES

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
••	•	Macon, Platt	44	18
CONTRACT NO. 74156			ILLINOIS FED. AID PROJECT	