



EXISTING PARTIAL PLAN

NOTES

Removal of existing expansion joint and associated material shall not be paid for separately but shall be included in the cost of Concrete Removal.
 Trim existing reinforcement to accommodate proposed expansion joint.
 See Sheet 11 of 22 for sections and view details.
 Stud Shear connectors damaged during concrete removal operations shall be removed and replaced per section 505 of the Standard Specifications. Cost included with Concrete Removal.

BILL OF MATERIAL

Item	Unit	Total
Concrete Removal	Cu. Yd.	98.1

SOUTH BOUND LANES -
 SUPERSTRUCTURE CONCRETE REMOVAL
 S.N.082-0241 (NB) & S.N. 082-0242 (SB)