

SUMMARY OF QUANTITIES

100% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005		
				MADISON COUNTY	BOND COUNTY	
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	152	152		
44200612	CLASS A PATCHES, TYPE III, 13 INCH	SQ YD	188	172	16	
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SQ YD	953	926	27	
44200616	CLASS A PATCHES, TYPE I, 14 INCH	SQ YD	12		12	
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SQ YD	255		255	
44200624	CLASS A PATCHES, TYPE III, 14 INCH	SQ YD	64		64	
44200628	CLASS A PATCHES, TYPE IV, 14 INCH	SQ YD	183		183	
44213000	PATCHING REINFORCEMENT	SQ YD	1807	1250	557	
44213200	SAW CUTS	FOOT	6934	4170	2764	
44213204	TIE BARS 3/4"	EACH	351	296	55	
67100100	MOBILIZATION	L SUM	1	0.7	0.3	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	28	18	10	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.7	0.3	

100% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005		
				MADISON COUNTY	BOND COUNTY	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	19	13	6	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1317	1317		
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	667		667	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	35	25	10	

*SPECIALTY ITEM

FILE NAME :	USER NAME : tharp1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pvc\work\pvidot\tharp1\48311563\4876915-sh1-plan.dgn	PLLOT SCALE = 1/8" = 1' / in.	DRAWN -	REVISED -			70	DIST 8 PATCHING 2013-3			7	3
	PLLOT DATE = 2/5/2013	CHECKED -	REVISED -			CONTRACT NO. 76G05					
		DATE -	REVISED -			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					