

SEEDING/EARTHWORK SCHEDULE

ROUTE LOCATION	MILE	STRUCTURE PROTECTED	DIRECTION PROTECTED	NOTES	COUNTY	URBAN/RURAL	SEEDING CLASS 2A ACRE	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	MULCH, METHOD 2 ACRE ²	TEMPORARY EROSION CONTROL SEEDING POUND	INLET AND PIPE PROTECTION EACH	EARTH EXCAVATION CU YD	FURNISHED EXCAVATION CU YD
I-70	15.80	SIGN TRUSS (8S0601070L015.8)	WB	I-55/70 HIGHWAY MERGER SIGN	MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		5
I-70	16.20	SIGN TRUSS (8S060107016.2)	WBS ¹	ITS MESSAGE BOARD	MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		10
I-70	17.60	PIER (060-0174)	EB	OLD STAUNTON RD	MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		2
			WB		MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
I-70	20.40	PIER (060-0108)	EB	IL 4 OVERPASS	MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		2
			WB		MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		3
I-70	21.60	PIER (060-0164)	EB	MARINE RD/ CO RD 13	MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		1
			WB		MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		1
I-70	24.00	PIER (060-0151)	EB	IL 143 OVERPASS, EXIT 24	MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		1
			WB		MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		2
I-70	26.00	PIER (060-0176)	EB	PRAIRIE RD OVERPASS	MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
			WB		MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1	2	
I-70	28.00	PIER (060-0132)	EB	IL 160 OVERPASS	MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1	5	10
			WB		MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
I-70	30.20	PIER (060-0079)	EB	US 40/STEINER RD OVERPASS	MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
			WB		MADISON	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		10
I-70	32.20	PIER (003-0042)	EB	BAUMANN RD MADISON/BOND CO	BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
			WB		BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		1
I-70	35.80	PIER (003-0015)	WB	POCAHONTAS, EXIT 36	BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		3
I-70	37.60	PIER (003-0016)	EB	US 40 OVERPASS	BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
			WB		BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
I-70	39.22	PIER (003-0043)	EB	SUGAR LOAF RD OVERPASS	BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
			WB		BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		2
I-70	41.40	PIER (003-0047)	EB	US 40, EXIT 41 MILLERSBURG RD	BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
			WB		BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
I-70	43.40	PIER (003-0044)	EB	DUDLEYVILLE RD	BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
			WB		BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
I-70	45.20	PIER (003-0031)	EB	IL 127, EXIT 45	BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		3
			WB		BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		3
I-70	52.20	PIER (003-0036)	EB	MULBERRY GROVE, EXIT 52	BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
			WB		BOND	RURAL	0.05	4.5	4.5	4.5	0.10	5	1		
CALCULATED QUANTITY							1.55	139.5	139.5	139.5	3.10	155	31	7	59
PLAN QUANTITY							1.55	140	140	140	3.10	155	31	7	59

1. "S" IN THE DIRECTION COLUMN REPRESENTS THE RIGHT "SHOULDER" FOR THAT DIRECTION.
2. THIS QUANTITY INCLUDES AN APPLICATION FOR TEMPORARY MULCH AND FINAL MULCH.

• VARIOUS
**DIST 8 ATTENUATOR 2013-1

FILE NAME =	USER NAME = wedmore_jb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-70 SCHEDULE OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pwork\pwork\wedmore_jb\d0322728\d076g13-sh-t-plan.dgn		DRAWN -	REVISED -						•	••		16	10
		CHECKED -	REVISED -						CONTRACT NO. 76G13				
		DATE -	REVISED -		SCALE:	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				