



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 11, 2013

SUBJECT: FAP Route 331 (IL 13)
Section (1-3)R-3
Williamson County
Contract No. 78259
Item No. 162, April 26, 2013 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Added page 109 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P. E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Jeffrey Keirn, Region 5, District 9; Mike Renner; Estimates

DB/ks

TABLE OF CONTENTS

LOCATION OF PROJECT 1

DESCRIPTION OF PROJECT 1

TRAFFIC CONTROL AND PROTECTION, (SPECIAL) 1

UTILITIES..... 2

POROUS GRANULAR BACKFILL 4

BORROW EXCAVATION 4

SUBGRADE 5

FENCE REMOVAL 5

THERMOPLASTIC PAVEMENT MARKING, SPECIAL (WET REFLECTIVE)..... 5

BUILDING REMOVAL - CASE IV (NO ASBESTOS) (BDE)..... 9

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 10

FRICTION AGGREGATE (BDE) 19

GRANULAR MATERIALS (BDE)..... 22

HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE) 23

LIQUIDATED DAMAGES (BDE)..... 24

PAYMENTS TO SUBCONTRACTORS (BDE) 24

PLACING AND CONSOLIDATING CONCRETE (BDE)..... 25

PORTLAND CEMENT CONCRETE (BDE) 28

RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE) 68

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) 78

REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE) 82

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 83

SYNTHETIC FIBERS IN CONCRETE GUTTER, CURB, MEDIAN, AND PAVED DITCH (BDE)..... 83

TEMPORARY EROSION AND SEDIMENT CONTROL (BDE)..... 84

TRACKING THE USE OF PESTICIDES (BDE)..... 84

TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) 84

IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION (TPG)..... 85

UTILITY COORDINATION AND CONFLICTS (BDE)..... 87

WARM MIX ASPHALT (BDE) 92

WEEKLY DBE TRUCKING REPORTS (BDE)..... 98

WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING (BDE) 98

WORKING DAYS (BDE) 99

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)..... 99

STORM WATER POLLUTION PREVENTION PLAN..... 102

SOFT SOILS 109

SOFT SOILS

Based on geotechnical investigation of the project area, it is anticipated that soft soils may be encountered in the following areas:

Alignment	Station	To	Station
North Frontage Road	30+50		34+50

If, in the opinion of the Engineer, these areas will not provide a suitable platform for embankment construction the contractor shall process the existing ground in accordance with Article 301.04 (b), this additional processing will not be paid for separately. After this has been performed, the Engineer will make a determination as to whether embankment construction may proceed or if the ground and soil conditions warrant undercut and removal. Any undercut material may be used elsewhere in the proposed embankment; however, the contractor should be aware that additional disking and drying may be required to meet the compaction and moisture requirements of the Standard Specifications and Special Provisions.

This work will not be paid for separately but shall be included in the contract unit price per cubic yard for EARTH EXCAVATION.

Added 4-11-2013