

CODE NUMBER	PAY ITEM	CONSTRUCTION TYPE CODE 0014	
		UNIT	STATE FUNDING 50% ILLINOIS & 50% KENTUCKY SN 064-0035
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	3074
44000155	HMA SURFACE REMOVAL 1 1/2"	SQ YD	36,600
50102400	CONCRETE REMOVAL	CU YD	143
50300255	CONCRETE SUPERSTRUCTURE	CU YD	148.3
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	14,670
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	19340
50800515	BAR SPLICERS	EACH	288
50800530	MECHANICAL SPLICERS	EACH	288
52000110	PREFORMED JOINT STRIP SEAL	FOOT	378
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	330
67000400	ENGINEER FIELD OFFICE, TYPE A	CAL MO	12
67100100	MOBILIZATION	L SUM	1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	4
70103815	TRAFFIC CONTROL SURVEILLANCE	CA DAY	30
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12

FILE NAME *	USER NAME = holsteadtw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
c:\pwwork\pwwork\holsteadtw\83268621	293-ahc-plen.dgn	DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	24	0SMART 2013-1	MASSAC	23	3
Default	PLOT SCALE = 100.0000 / 1/8"	CHECKED -	REVISED -								CONTRACT NO. 78293				
	PLOT DATE = 2/1/2013	DATE -	REVISED -						ILLINOIS FED. AID PROJECT						