

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE-0005	
		FUNDING	80 % FEDERAL 20 % STATE
		UNIT	QUANTITY
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	225
X4421000	PARTIAL DEPTH PATCHING	TON	15
Z0034105	MATERIAL TRANSFER DEVICE	TON	5504
40600100	BITUMINOUS MATERIAL (PRIME COAT)	GALLOW	7610
40600300	AGGREGATE (PRIME COAT)	TON	132
40600647	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	1528
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	209
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	200
40600990	TEMPORARY RAMP	SO YD	57
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N90	TON	3976
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	41
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	17644
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	100
44022025	PARTIAL DEPTH REMOVAL 2"	SO YD	81
44201299	DOWEL BARS 1 1/2"	EACH	6628

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE-0005	
		FUNDING	80 % FEDERAL 20 % STATE
		UNIT	QUANTITY
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SO YD	4
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	2649
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SO YD	1088
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SO YD	156
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SO YD	756
44213200	SAW CUTS	FOOT	15864
44213204	TIE BARS 3/4"	EACH	266
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	13779
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1098
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	FOOT	100
67100100	MOBILIZATION	L SUM	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1