

**PAVEMENT MARKING SCHEDULE**

LOCATION STATION TO STATION	PAINT PAVEMENT MARKING				THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	REMARKS
	LINE 4"							
	YELLOW		WHITE					
	SOLID FOOT	SKIP DASH FOOT	SOLID FOOT	SKIP DASH FOOT				
<b>IL 3 / US 51</b>								
289+44 TO 290+80	272		408	68				
290+40						20.6		
290+80 TO 301+56	2152		2152	538				
301+56 TO 302+32			152	38				
302+32 TO 303+58.14 BK	252		378	63				
303+42						20.6		
771+76.77 AH TO 773+07	260		391	65				
773+07 TO 782+40	1866		1866	467				
782+40 TO 782+98			116	29				
782+98 TO 784+90	384		576	96				
783+53						20.6		
784+90 TO 790+00	1020		1020	255				
790+00 TO 790+50			100	25				
790+50 TO 792+71	442		663	111				
791+18						20.6		
792+71 TO 793+00	58		58	15				
793+00 TO 799+68	1336			334				
799+68 TO 799+91.	148			12	61			
800+44 TO 801+44	400		100		20			
800+47						41.5		
801+22						20.6		
800+97						41.5		
801+44 TO 804+25.28 BK	1125				132			
804+27.4 AH TO 821+40.	3425	856				105.6	SEE GENERAL NOTE #10	
817+54					27			
817+79						122.4		
818+04					27			
819+28					27			
819+64					27			
821+14					27			
821+39						122.4		
821+40 TO 821+81	100				47			
823+11					27			
822+35 TO 823+35	200		100					
823+35 TO 824+35	200							
824+35 TO 841+96	3522	881				105.6	SEE GENERAL NOTE #10	
841+96 TO 844+06	840				110			
843+34						41.5		
843+77						41.5		
844+06 TO 845+06	200			50				
CLASS B PATCHES			1074	1074				
SUBTOTALS	18203	1737	9154	3238				
TOTALS			32332		370	162	725	

**ENTRANCE AND SIDEROAD SCHEDULE**

LOCATION STATION TO STATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	INCIDENTAL HOT-MIX ASPHALT SURFACING	REMARKS
	SO YD	TON	
<b>IL 3 / US 51</b>			
299+55 RT		2.0	
302+05 RT	49	8.8	
782+70 RT	42	7.5	
782+70 LT		1.4	
790+28 RT	51	8.8	
793+66 RT		2.0	
795+46 RT		2.2	
799+96 LT		2.5	
800+11 RT		3.2	
804+52 RT		2.6	
TOTALS	142	41	

**SIGNAGE SCHEDULE**

LOCATION STATION TO STATION	SIGN PANEL - TYPE I	METAL POST - TYPE B	REMARKS
	SO FT	FOOT	
<b>IL 3 / US 51</b>			
794+00 RT	6.25	15	W9-1L
799+00 RT	6.25	15	W4-2L
806+50 RT	6	14	R3-9b
825+00 RT & LT	12	28	(2) R3-9b
840+50 LT	6	14	R3-9b
846+00 LT	6.25	15	W4-2L
851+00 LT	6.25	15	W9-1L
TOTALS	49	116	