

GAZENOVIA TOWNSHIP					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ FT)	AREA - TY 2 (SQ FT)
OBJECT MARKER, TY 3 - LEFT	OM3-L	12X36	37	111.00	
OBJECT MARKER, TY 3 - RIGHT	OM3-R	12X36	37	111.00	
STOP	R1-1	30X30	24	150.00	
SPEED LIMIT 25	R2-1	24X30	2	10.00	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	28	84.00	
TURN LEFT	W1-1L	30X30	7	43.75	
TURN RIGHT	W1-1R	30X30	8	50.00	
CURVE LEFT	W1-2L	30X30	6	37.50	
CURVE RIGHT	W1-2R	30X30	5	31.25	
REVERSE TURN LEFT	W1-3L	30X30	1	6.25	
REVERSE CURVE LEFT	W1-4L	30X30	5	31.25	
REVERSE CURVE RIGHT	W1-4R	30X30	3	18.75	
WINDING ROAD LEFT	W1-5L	30X30	4	25.00	
WINDING ROAD RIGHT	W1-5R	30X30	1	6.25	
ONE DIRECTION LARGE ARROW	W1-6	48X24	8	64.00	
TWO DIRECTION LARGE ARROW	W1-7	48X24	13	104.00	
CHEVRON ALIGNMENT LEFT	W1-8L	18X24	19	57.00	
CHEVRON ALIGNMENT RIGHT	W1-8R	18X24	19	57.00	
CURVE LEFT WITH SIDE ROAD RIGHT	W1-10L	36X36	1	9.00	
CURVE RIGHT WITH SIDE ROAD LEFT	W1-10R	36X36	1	9.00	
INTERSECTION WARNING CROSSROAD	W2-1	30X30	6	37.50	
INTERSECTION WARNING T-SYMBOL	W2-4	30X30	9	56.25	
STOP AHEAD SYMBOL	W3-1	30X30	23	143.75	
REDUCED SPEED LIMIT AHEAD 25 MPH	W3-5	36X36	3	27.00	
CROSS TRAFFIC DOES NOT STOP	W4-1100	30X18	4	15.00	
ROAD NARROWS	W5-1	30X30	1	6.25	
ONE LANE BRIDGE	W5-3	30X30	1	6.25	
HILL SYMBOL	W7-1	30X30	3	18.75	
PAVEMENT ENDS	W8-3	36X36	5	45.00	
LOOSE GRAVEL	W8-7	36X36	3	27.00	
ROUGH ROAD	W8-8	36X36	1	9.00	
ADVISORY SPEED (PLAQUE) 20 MPH	W13-1P	18X18	2	4.50	
ADVISORY SPEED (PLAQUE) 35 MPH	W13-1P	18X18	2	4.50	
DEAD END	W14-1	30X30	1	6.25	
NO OUTLET	W14-2	30X30	2	12.50	
		TOTAL	295	1435.5	0.0

PAY ITEM NUMBER	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH		298
Z0051398	REMOVE EXISTING SIGN POST	EACH		24
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	0
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH		0
	ASSEMBLY FOR TELESCOPING POST,	EACH		3
72900100	METAL POST, TY A	FOOT	12	0
72900200	METAL POST, TY B	FOOT	12	0
	ASSEMBLY FOR METAL POST,	EACH		70
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	288
	ASSEMBLY FOR WOOD POST,	EACH		233
X7350010	SIGN SUPPORT BRACKET	EACH		11

1. Incidental items. See special provisions.

CLAYTON TOWNSHIP					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ FT)	AREA - TY 2 (SQ FT)
OBJECT MARKER, TY 3 - LEFT	OM3-L	12X36	15	45.00	
OBJECT MARKER, TY 3 - RIGHT	OM3-R	12X36	19	57.00	
OBJECT MARKER, TY 4	OM4-3	18X18	4	9.00	
STOP	R1-1	30X30	33	206.25	
YIELD	R1-2	36X36X36	1	3.90	
ROAD ENDS	R11-1100	36X30	1	7.50	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	26	78.00	
CURVE LEFT	W1-2L	30X30	2	12.50	
CURVE RIGHT	W1-2R	30X30	3	18.75	
REVERSE CURVE RIGHT	W1-4R	30X30	5	31.25	
ONE DIRECTION LARGE ARROW	W1-6	48X24	7	56.00	
TWO DIRECTION LARGE ARROW	W1-7	48X24	8	64.00	
CHEVRON ALIGNMENT RIGHT	W1-8R	18X24	1	3.00	
INTERSECTION WARNING T-SYMBOL	W2-4	30X30	7	43.75	
STOP AHEAD SYMBOL	W3-1	30X30	21	131.25	
CROSS TRAFFIC DOES NOT STOP	W4-1100	30X18	3	11.25	
ROAD ENDS 500 FT	W8-1108	30X30	1	6.25	
ADVISORY SPEED (PLAQUE) 30 MPH	W13-1P	18X18	1	2.25	
ADVISORY SPEED (PLAQUE) 40 MPH	W13-1P	18X18	4	9.00	
DEAD END	W14-1	30X30	2	12.50	
		TOTAL	164	808.4	0.0

PAY ITEM NUMBER	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH		165
Z0051398	REMOVE EXISTING SIGN POST	EACH		28
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	336
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH		28
	ASSEMBLY FOR TELESCOPING POST,	EACH		35
72900100	METAL POST, TY A	FOOT	12	0
72900200	METAL POST, TY B	FOOT	12	0
	ASSEMBLY FOR METAL POST,	EACH		14
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0
	ASSEMBLY FOR WOOD POST,	EACH		127
X7350010	SIGN SUPPORT BRACKET	EACH		11

1. Incidental items. See special provisions.

DESIGNED - KK	REVISED - KK 01/30/2013
DRAWN - KK	REVISED -
CHECKED - BWI	REVISED -
DATE - 08/14/12	REVISED -

Woodford County
Highway Department

Township Schedule

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00016-00-5G	Woodford	18	04
FEDERAL-AID PROJECT			CONTRACT NO.: 89628	

SCALE: SHEET NO. 04 OF 18 SHEETS STA. TO STA.