

GREENE TOWNSHIP					
ITEM DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
OBJECT MARKER, TY 3 - LEFT	OM3-L	12X36	16	48.00	
OBJECT MARKER, TY 3 - RIGHT	OM3-R	12X36	27	81.00	
RED OBJECT MARKER, TY 4	OM4-3	18X18	6	13.50	
STOP	R1-1	30X30	29	181.25	
ROAD ENDS	R11-2	36X30	2	15.00	
BRIDGE WEIGHT LIMIT - TONS SV COMBO 28T 28T	R12-1100	54X42	3		47.25
1.4 MILES AHEAD	R12-1102P	54X12	1	4.50	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	36	108.00	
TURN LEFT	W1-1L	36X36	6	54.00	
TURN RIGHT	W1-1R	36X36	6	54.00	
CURVE LEFT	W1-2L	30X30	1	6.25	
REVERSE TURN LEFT	W1-3L	30X30	4	25.00	
REVERSE TURN RIGHT	W1-3R	30X30	1	6.25	
REVERSE CURVE LEFT	W1-4L	30X30	6	37.50	
REVERSE CURVE RIGHT	W1-4R	30X30	1	6.25	
WINDING ROAD LEFT	W1-5L	30X30	1	6.25	
WINDING ROAD RIGHT	W1-5R	30X30	1	6.25	
ONE DIRECTION LARGE ARROW	W1-6	48X24	2	16.00	
TWO DIRECTION LARGE ARROW	W1-7	48X24	15	120.00	
CHEVRON ALIGNMENT LEFT	W1-8L	18X24	4	12.00	
CHEVRON ALIGNMENT RIGHT	W1-8R	18X24	1	3.00	
INTERSECTION WARNING - SIDE ROAD RIGHT	W2-2R	30X30	1	6.25	
INTERSECTION WARNING - T-SYMBOL	W2-4	30X30	1	6.25	
STOP AHEAD SYMBOL	W3-1	30X30	15	93.75	
CROSS TRAFFIC DOES NOT STOP	W4-1100	30X18	3	11.25	
ONE LANE BRIDGE	W5-3	30X30	1	6.25	
HILL (SYMBOL)	W7-1	30X30	1	6.25	
HILL BLOCKS VIEW	W7-6	30X30	8	50.00	
PAVEMENT ENDS	W8-3	36X36	1	9.00	
LOOSE GRAVEL	W8-7	36X36	2	18.00	
LOW SHOULDER	W8-9	36X36	4	36.00	
WATCH FOR ICE ON BRIDGE	W8-1102	36X36	2	18.00	
ADVISORY SPEED (PLAQUE) 10 MPH	W13-1P	18X18	2	4.50	
ADVISORY SPEED (PLAQUE) 20 MPH	W13-1P	18X18	1	2.25	
ADVISORY SPEED (PLAQUE) 25 MPH	W13-1P	18X18	2	4.50	
DEAD END	W14-1	30X30	3	18.75	
ROAD CLOSED 500FT	W20-3	30X30	2	12.50	
			TOTAL	218	47.3

PAY ITEM NUMBER	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH		218
Z0051398	REMOVE EXISTING SIGN POST	EACH		24
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	288
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH		24
	ASSEMBLY FOR TELESCOPING POST,	EACH		26
72900100	METAL POST, TY A	FOOT	12	0
72900200	METAL POST, TY B	FOOT	12	0
	ASSEMBLY FOR METAL POST,	EACH		49
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0
	ASSEMBLY FOR WOOD POST,	EACH		160
X7350010	SIGN SUPPORT BRACKET	EACH		17

1. Incidental items. See special provisions.

KANSAS TOWNSHIP					
ITEM DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
OBJECT MARKER, TY 3 - LEFT	OM3-L	12X36	11	33.00	
OBJECT MARKER, TY 3 - RIGHT	OM3-R	12X36	17	51.00	
OBJECT MARKER, TY 4	OM4-3	18X18	3	6.75	
STOP	R1-1	30X30	4	25.00	
YIELD	R1-2	36X36X36	4	15.58	
SPEED LIMIT 35	R2-1	24X36	4	24.00	
SPEED LIMIT 40	R2-1	24X36	3	18.00	
KEEP (ARROW) RIGHT	R4-7A	24X30	1	5.00	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	5	15.00	
TURN LEFT	W1-1L	30X30	3	18.75	
TURN RIGHT	W1-1R	30X30	3	18.75	
CURVE LEFT	W1-2L	30X30	8	50.00	
CURVE RIGHT	W1-2R	30X30	7	43.75	
WINDING ROAD LEFT	W1-5L	30X30	3	18.75	
WINDING ROAD RIGHT	W1-5R	30X30	1	6.25	
CHEVRON ALIGNMENT LEFT	W1-8L	18X24	1	3.00	
CHEVRON ALIGNMENT RIGHT	W1-8R	18X24	3	9.00	
INTERSECTION WARNING - SIDE ROAD RIGHT	W2-2R	30X30	1	6.25	
INTERSECTION WARNING - T-SYMBOL	W2-4	30X30	3	18.75	
STOP AHEAD SYMBOL	W3-1	30X30	7	43.75	
HILL (SYMBOL)	W7-1	30X30	1	6.25	
ADVISORY SPEED (PLAQUE) 20 MPH	W13-1P	18X18	1	2.25	
DEAD END	W14-1	30X30	4	25.00	
NO OUTLET	W14-2	30X30	1	6.25	
			TOTAL	99	470.1
					0.0

PAY ITEM NUMBER	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH		100
Z0051398	REMOVE EXISTING SIGN POST	EACH		54
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	0
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH		0
	ASSEMBLY FOR TELESCOPING POST,	EACH		0
72900100	METAL POST, TY A	FOOT	12	0
72900200	METAL POST, TY B	FOOT	12	0
	ASSEMBLY FOR METAL POST,	EACH		27
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	54
	ASSEMBLY FOR WOOD POST,	EACH		74
X7350010	SIGN SUPPORT BRACKET	EACH		0

1. Incidental items. See special provisions.

DESIGNED	KK	REVISED	KK 01/30/2015
DRAWN	KK	REVISED	
CHECKED	BWI	REVISED	
DATE	10/19/12	REVISED	

Woodford County
Highway Department

Township Schedule

SCALE: SHEET NO. 06 OF 18 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-0016-00-SC	Woodford	18	06
	FEDERAL-AID PROJECT		CONTRACT NO. 09628	