

PANOLA TOWNSHIP					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
OBJECT MARKER, TY 3 - LEFT	OM3-L	12X36	13	39.00	
OBJECT MARKER, TY 3 - RIGHT	OM3-R	12X36	16	48.00	
STOP	R1-1	30X30	39	243.75	
BRIDGE WEIGHT LIMIT - TONS SV 14T COMBO 18T 22T	R12-1100	54X42	4		63.00
0.4 MILES AHEAD	R12-1102P	54X12	1	4.50	
0.5 MILES AHEAD	R12-1102P	54X12	1	4.50	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	5	15.00	
SCHOOL BUS STOP AHEAD	S3-1	36X36	1	9.00	
TURN LEFT	W1-1L	30X30	1	6.25	
REVERSE CURVE LEFT	W1-4L	30X30	4	25.00	
REVERSE CURVE RIGHT	W1-4R	30X30	2	12.50	
TWO DIRECTION LARGE ARROW	W1-7	48X24	2	16.00	
STOP AHEAD SYMBOL	W3-1	30X30	11	68.75	
PAVEMENT ENDS	W8-3	36X36	4	36.00	
LOOSE GRAVEL	W8-7	36X36	3	27.00	
ADVISORY SPEED (PLAQUE) 25 MPH	W13-1P	18X18	1	2.25	
DEAD END	W14-1	30X30	2	12.50	
			TOTAL	110	63.0

PAY ITEM NUMBER	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL			110
Z0051398	REMOVE EXISTING SIGN POST			28
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	12	0	0
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE			0
	ASSEMBLY FOR TELESCOPING POST,			1
72900100	METAL POST, TY A	12	0	0
72900200	METAL POST, TY B	12	0	0
	ASSEMBLY FOR METAL POST,			14
X7300105	WOOD SUPPORT, 4' X 4'	12	28	336
X7300105	WOOD SUPPORT, 4' X 6'	12	0	0
	ASSEMBLY FOR WOOD POST,			99
X7350010	SIGN SUPPORT BRACKET			4

1. Incidental items. See special provisions.

PARTRIDGE TOWNSHIP					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
OBJECT MARKER, TY 3 - LEFT	OM3-L	12X36	6	18.00	
OBJECT MARKER, TY 3 - RIGHT	OM3-R	12X36	10	30.00	
STOP	R1-1	30X30	8	50.00	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	9	27.00	
TURN LEFT	W1-1L	30X30	16	100.00	
TURN RIGHT	W1-1R	30X30	17	106.25	
CURVE LEFT	W1-2L	30X30	6	37.50	
CURVE RIGHT	W1-2R	30X30	6	37.50	
REVERSE TURN LEFT	W1-3L	30X30	2	12.50	
REVERSE TURN RIGHT	W1-3R	30X30	2	12.50	
REVERSE CURVE LEFT	W1-4L	30X30	1	6.25	
REVERSE CURVE RIGHT	W1-4R	30X30	3	18.75	
WINDING ROAD LEFT	W1-5L	30X30	11	68.75	
WINDING ROAD RIGHT	W1-5R	30X30	7	43.75	
ONE DIRECTION LARGE ARROW	W1-6	48X24	35	280.00	
TWO DIRECTION LARGE ARROW	W1-7	48X24	7	56.00	
CHEVRON ALIGNMENT LEFT	W1-8L	18X24	7	21.00	
CHEVRON ALIGNMENT RIGHT	W1-8R	18X24	7	21.00	
INTERSECTION WARNING - SIDE ROAD (Y) LEFT	W2-3L	30X30	4	25.00	
INTERSECTION WARNING T-SYMBOL	W2-4	30X30	4	25.00	
STOP AHEAD SYMBOL	W3-1	30X30	10	62.50	
HILL SYMBOL	W7-1	30X30	4	25.00	
BUMP	W8-1	30X30	2	12.50	
PAVEMENT ENDS	W8-3	36X36	2	18.00	
ADVISORY SPEED (PLAQUE) 10 MPH	W13-1P	18X18	2	4.50	
ADVISORY SPEED (PLAQUE) 15 MPH	W13-1P	18X18	40	90.00	
ADVISORY SPEED (PLAQUE) 20 MPH	W13-1P	18X18	28	63.00	
DEAD END	W14-1	30X30	2	12.50	
HIDDEN ENTRANCE	W16-1101	30X30	1	6.25	
BLIND ENTRANCE	W16-1101	30X30	1	6.25	
			TOTAL	260	1297.3
					0.0

PAY ITEM NUMBER	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL			260
Z0051398	REMOVE EXISTING SIGN POST			17
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	12	0	0
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE			0
	ASSEMBLY FOR TELESCOPING POST,			1
72900100	METAL POST, TY A	12	0	0
72900200	METAL POST, TY B	12	0	0
	ASSEMBLY FOR METAL POST,			12
X7300105	WOOD SUPPORT, 4' X 4'	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	12	17	204
	ASSEMBLY FOR WOOD POST,			250
X7350010	SIGN SUPPORT BRACKET			3

1. Incidental items. See special provisions.

DESIGNED - KK	REVISED - KK 01/30/2013
DRAWN - KK	REVISED -
CHECKED - BWT	REVISED -
DATE - 10/19/12	REVISED -

Woodford County
Highway Department

Township Schedule

SCALE: _____	SHEET NO. 10 OF 10 SHEETS	STA. _____ TO STA. _____	F.A. RTE. _____	SECTION 10-0006-00-SC	COUNTY Woodford	TOTAL SHEETS 10	SHEET NO. 10
			FEDERAL-AID PROJECT		CONTRACT NO.: 89628		