

VILLAGE OF GERMANTOWN HILLS					
DESCRIPTION	MUTCD	SIZE	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ.FT)	AREA - TY 2 (SQ.FT)
RED OBJECT MARKER	OM4-1	18X18	3	6.75	
STOP	R1-1	30X30	88	550.00	
YIELD	R1-2	36X36X36	12	46.75	
ALL WAY PLAQUE	R1-3P	18X06	20	15.00	
SPEED LIMIT 20	R2-1	24X30	9	45.00	
SPEED LIMIT 25	R2-1	24X30	32	160.00	
SPEED LIMIT 30	R2-1	24X30	13	65.00	
SPEED LIMIT 35	R2-1	24X30	3	15.00	
SPEED LIMIT 40	R2-1	24X30	1	5.00	
DO NOT PASS	R4-1	24X30	3	15.00	
SCHOOL	S1-1	30X30	1	6.25	
SCHOOL SPEED LIMIT	S4-1100	24X48	1	8.00	
CURVE LEFT	W1-2L	30X30	2	12.50	
CURVE RIGHT	W1-2R	30X30	2	12.50	
STOP AHEAD SYMBOL	W3-1	30X30	3	18.75	
REDUCED SPEED LIMIT AHEAD 20	W3-5	36X36	1	9.00	
REDUCED SPEED LIMIT AHEAD 25	W3-5	36X36	1	9.00	
TRAFFIC FROM RIGHT DOES NOT STOP	W4-4aP	24X12	1	2.00	
TRAFFIC FROM LEFT DOES NOT STOP	W4-4aP	24X12	1	2.00	
ONCOMING TRAFFIC DOES NOT STOP	W4-4bP	24X12	1	2.00	
PEDESTRIAN	W11-2	30X30	2	12.50	
FIRETRUCK	W11-8	30X30	2	12.50	
ADVISORY SPEED (PLAQUE) 5 MPH	W13-1P	18X18	1	2.25	
ADVISORY SPEED (PLAQUE) 35 MPH	W13-1P	18X18	1	2.25	
DEAD END	W14-1	30X30	10	62.50	
NO OUTLET	W14-2	30X30	3	18.75	
PLAYGROUND SYMBOL	W15-1	30X30	1	6.25	
		TOTAL	218	1122.5	0.0

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH			218
Z0051398	REMOVE EXISTING SIGN POST	EACH			0
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	0	0
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			0
	ASSEMBLY FOR TELESCOPING POST,	EACH			5
72900100	METAL POST, TY A	FOOT	12	0	0
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST,	EACH			201
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST,	EACH			12
X7350010	SIGN SUPPORT BRACKET	EACH			0

1. Incidental items. See special provisions.

VILLAGE OF GOODFIELD					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ.FT)	AREA - TY 2 (SQ.FT)
STOP	R1-1	30X30	21	131.25	
YIELD	R1-2	36X36X36	4	15.58	
SPEED LIMIT 20	R2-1	24X30	15	75.00	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	5	15.00	
SCHOOL SPEED ZONE AHEAD (SYMBOL)	S4-5	36X36	1	9.00	
SCHOOL SPEED LIMIT	S4-1100	24X48	3	24.00	
STOP AHEAD SYMBOL	W3-1	30X30	1	6.25	
RAILROAD AHEAD	W10-1	36 DIA	3	27.00	
CAUTION 60 FT BETWEEN TRACKS AND HIGHWAY	W10-1100	30X36	1	7.50	
NO OUTLET	W14-2	30X30	3	18.75	
TRUCK ENTRANCE	W16-1101	30X30	1	6.25	
		TOTAL	58	335.6	0.0

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH			59
Z0051398	REMOVE EXISTING SIGN POST	EACH			0
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	0	0
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			0
	ASSEMBLY FOR TELESCOPING POST,	EACH			3
72900100	METAL POST, TY A	FOOT	12	0	0
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST,	EACH			3
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST,	EACH			52
X7350010	SIGN SUPPORT BRACKET	EACH			0

1. Incidental items. See special provisions.

VILLAGE OF KARPA					
DESCRIPTION	MUTCD	SIZE	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ.FT)	AREA - TY 2 (SQ.FT)
STOP	R1-1	30X30	13	81.25	
YIELD	R1-2	36X36X36	1	3.90	
SPEED LIMIT 20	R2-1	24X30	15	75.00	
ROAD CLOSED	R11-2	48X30	1		10.00
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	7	21.00	
DEAD END	W14-1	30X30	5	31.25	
PLAYGROUND SYMBOL	W15-1	30X30	1	6.25	
		TOTAL	43	218.6	10.0

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH			43
Z0051398	REMOVE EXISTING SIGN POST	EACH			2
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	2	24
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			2
	ASSEMBLY FOR TELESCOPING POST,	EACH			13
72900100	METAL POST, TY A	FOOT	12	0	0
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST,	EACH			0
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST,	EACH			30
X7350010	SIGN SUPPORT BRACKET	EACH			0

1. Incidental items. See special provisions.

DESIGNED	KK	REVISED	KK 01/30/2013
DRAWN	KK	REVISED	-
CHECKED	BWI	REVISED	-
DATE	10/19/12	REVISED	-

Woodford County
Highway Department

Municipal Schedule

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00016-00-50	Woodford	18	15
CONTRACT NO. 89628				

SCALE: SHEET NO. 15 OF 18 SHEETS STA. TO STA.